



18" Concrete Pad will be buried 4' under ground and spaced 5' apart

6x6 PT Post will sit on Pad and support carrying beam

