



BOILERS (/PRODUCTS/BOILERS)

> RESIDENTIAL BOILERS (/PRODUCTS/RESIDENTIAL-BOILERS) > SGO OIL BOILER



## SGO Oil Boiler

- Oil-fired steam boiler with cast iron sections and tankless heater opening
- Has large water content for longer steaming times
- Two flue outlets- rear and top - for complete venting flexibility
- Includes factory-wired circulator, service switch and Weil-McLain exclusive captured elastomer seals for added reliability
- Quick open top and swing-away burner door with full chamber access increase visibility for inspection and servicing
- Recessed target wall design protects unit from flue brushes
- 84% AFUE

### Share product info

» [Email this page \(/forward?path=products/sgo-oil-boiler\)](#)

[Technical Data](#)

[Downloads](#)

## Technical Data

Model	AFUE (%)	CSA Input (MBH)	Steam (Sq. Ft.)	DOE Heating Cap. (MBH)	Net AF
SGO-3	84	0.95	354	114	
SGO-4	84	1.2	450	144	
SGO-5	83.9	1.45	546	174	
SGO-6	83.7	1.75	658	210	
SGO-7	83.6	2	750	240	
SGO-8					