Inspections Division
Date: 07/08/14

WINDOW SCHEDULE (MARVIN INTEGRITY WOOD-ULTREX SERIES)

	W X H	
A1 DOUBLE HUNG	4'4" X 4'8 1/4"	ITDH 2656 SW
A2 DOUBLE HUNG	6'2" X 4'4"	ITDH 3652 SW
A3 AWNING	3'6 1/2" X 2'3 5/8"	IAWN 2527 ZW
A4 DOUBLE HUNG	3'0 1/2" X 3'01/4"	ITDH 4236 (TEMPARED GLASS)
A5 AWNING	6'1" X 3'3 5/8"	IAWN 3729 ZW
A6 DOUBLE HUNG	3'0 1/2" X 5'01/4"	ITDH 3660 E
A7 DOUBLE HUNG	6'0" X 5'01/4"	ITDH 3660 ZWE
B1 DOUBLE HUNG	2'6 1/2" X 3'0 1/4"	ITDH 3036
B2 DOUBLE HUNG	3'01/2" X 4'01/4"	ITDH 3648
B3 DOUBLE HUNG	3'01/2" X 4'01/4"	ITDH 3648
B4 DOUBLE HUNG	6'0" X 4'01/4"	ITDH 3648 ZW
B5 DOUBLE HUNG	3'0 1/2" X 5'01/4"	ITDH 3660 E
B6 TRANSOM	4'1" X 1'7 5/8"	ICAP 4919
B7 AWNING	2'1" X 3'3 5/8"	IAWN 2539
B8 AWNING	3'1" X 3'3 5/8"	IAWN 3739
C1 DOUBLE HUNG	4'4" X 4'8 1/4"	ITDH 2656 ZW
C2 DOUBLE HUNG	6'0" X 4'0 1/4"	ITDH 3648 ZW
C3 DOUBLE HUNG	2'8 1/2" X 4'01/4"	ITDH 3248
C4 DOUBLE HUNG	3'0 1/2" X 5'01/4"	ITDH 3660 E
C5 DOUBLE HUNG	2'8 1/2" X 4'01/4"	ITDH 3248
C6 DOUBLE HUNG	2'8 1/2" X 5'01/4"	ITDH 3260
C7 DOUBLE HUNG	3'01/2" X 5'01/4"	ITDH 3660 E
C8 DOUBLE HUNG	2'8 1/2" X 5'01/4"	ITDH 3260
C9 DOUBLE HUNG	6'0" X 5'01/4"	ITDH 3660 ZWE
D1 DOUBLE HUNG	6'0" X 4'0 1/4"	ITDH 3648 ZW
D2 DOUBLE HUNG	3'01/2" X 4'01/4"	ITDH 3648
D3 DOUBLE HUNG	3'01/2" X 4'01/4"	ITDH 3648
D4 DOUBLE HUNG	3'01/2" X 4'01/4"	ITDH 3648
D5 DOUBLE HUNG	3'01/2" X 4'01/4"	ITDH 3648
D6 DOUBLE HUNG	3'01/2" X 4'01/4"	ITDH 3648
D7 DOUBLE HUNG	3'01/2" X 5'01/4"	ITDH 3660 E
D8 DOUBLE HUNG	3'01/2" X 5'01/4"	ITDH 3660 E
D9 DOUBLE HUNG	3'01/2" X 5'01/4"	ITDH 3660 E
D10 DOUBLE HUNG	3'01/2" X 5'01/4"	ITDH 3660 E
D11 DOUBLE HUNG	3'01/2" X 5'01/4"	ITDH 3660 E
D12 DOUBLE HUNG	6'0" X 5'01/4"	ITDH 3660 ZWE

1. PROVIDE SCREENS OR ALL WINDOWS.
2. COLOR, HARDWARE FINISH, DIVIDED LITES AND EXTERIOR TRIM BY CONTRACTOR AND OWNER.
3. INSULATING GLASS ARGON LoE-180. VERIFY THERMAL PERFORMANCE U-FACTOR 0.31 DOUBLE HUNG, 0.30 AWNING

EXTERIOR DOOR SCHEDULE (MARVIN INTEGRITY WOOD-ULTREX SERIES)

1		
2	3'0" X 6'8"	IIFD 3065 X-L REAR ENTRY
3	2'6" X 6'8"	IIFD 2665 X-R 2ND FLOOR DECK

1. PROVIDE SCREEN DOORS.
2. COLOR, HARDWAREs FINISH, DIVIDED LITES AND EXTERIOR TRIM BY CONTRACTOR AND OWNER.
3. INSULATING GLASS ARGON LoE-272. VERIFY THERMAL PERFORMANCE U-FACTOR 0.30

NOTES:

1. WHERE PORCH LEVEL IS OVER 30" PROVIDE GUARD RAILS AS PER CODE.

REGISTERED ARCHITECT
JAMES AVERY STERLING
NO. 1076
STATE OF MAINE

James Sterling, AIA
142 High Street
Portland, Maine

ELEVATIONS