

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

SHALOM HOUSE INC /High Tech Fire Protection

Located at

503 WOODFORD ST

PERMIT ID: 2013-02108

ISSUE DATE: 11/07/2013

CBL: 184 C004001

has permission to **Install WB Fire Suppression**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.	A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
--	--

/s/ Chris Pirone

/s/ Tammy Munson

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

one handicap family unit on 1st & 2nd floor & one dwelling unit on 3rd floor

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

FP Sprinkler

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2013-02108	Date Applied For: 09/18/2013	CBL: 184 C004001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: One handicap family unit on 1st & 2nd floor and one dwelling unit on 3rd floor		Proposed Project Description: Install WB Fire Suppression		
Dept: Zoning	Status: Approved	Reviewer: Marge Schmuckal	Approval Date: 09/26/2013	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
Dept: Fire	Status: Approved w/Conditions	Reviewer: Chris Pirone	Approval Date: 11/05/2013	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) Shall comply with NFPA 13R. 2) The Standpipe system shall be installed in accordance with NFPA 14. Signed contractor's test certificate(s) are required. 3) The standpipe fire department connection shall have 2 1/2" inlets. 4) 14:6.3.8 Signs for Room Identification, Valves, and Hose Connections. et al. 14:6.4.5.2 Each fire department connection shall be designated by a sign having letters, at least 1 in. in height, that reads "STANDPIPE." 14:6.4.5.2.2 A sign also shall indicate the pressure required at the inlets to deliver the system demand. 14:6.6 Installation of signs. Signs shall be secured to a device or the building wall with corrosion-resistant chains or fasteners 5) This system is a manual wet standpipe. Each hose connection shall be provided with a conspicuous sign that reads "MANUAL STANDPIPE FOR FIRE DEPARTMENT USE ONLY."(14:5.4.2) Letters shall be red with a white background and shall be 2 1/2" in height. (14:6.3.8.5.2) 6) The Standpipe system shall be installed in accordance with the City of Portland Fire Department Regulations and NFPA 14 as published. A copy of the Contractor's Material and Test Certificates (NFPA 14 figure 11.1.3(a) and (b) if pertinent) shall be provided prior to scheduling of the final inspection. 7) A 4100 series Knox Box is required. 8) The approved plans with the Building Department Approved stamp shall be maintained on site for inspection. 9) Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector. 10 The entire sprinkler system shall be maintained in accordance with NFPA 25, Standard for Inspection, Testing and Maintenance of Water-Based Fire Protection Systems, 2008 edition. 11 System acceptance and commissioning must be coordinated with a fire alarm technician and suppression system contractors and the Fire Department. Call 874-8400 to schedule. 12 Fire department connection shall be 2 1/2" inlets. 13 Sprinkler supervision shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code.				