

Skylight types



30%*
Federal tax credit on skylight.

Solar powered fresh air skylights

- Features a solar panel to recharge a highly efficient battery powered operator and control system.
- Integrated rain sensor will close the skylight automatically, in case of inclement weather.
- VELUX INTEGRA® control pad included. Easy-to-use touch screen with descriptive icons.

Deck mounted - Model VSS
Curb mounted - Model VCS

* For more information visit www.veluxusa.com/taxcredits



Deck mounted - Model VSE
Curb mounted - Model VCE

Electric fresh air skylights

- Single hard wire connects into a standard junction box.
- Integrated rain sensor will close the skylight automatically, in case of inclement weather.
- VELUX INTEGRA® control pad included. Easy-to-use touch screen with descriptive icons.



Deck mounted - Model VS
Curb mounted - Model VCM

Manual fresh air skylights

- Opens and closes manually with VELUX control rods when out of reach (sold separately).
- Smooth-turning handle available for when the skylight is installed within reach.
- Factory-installed blinds available.



Deck mounted - Model FS, FSR
Curb mounted - Model FCM
Self-flashed - Model QPF

Fixed skylights

- Economical choice to transform dark spaces with natural light.
- Factory-installed blinds available.

Flashing systems

Our engineered flashing provides a weather-tight installation, and is required for the **No Leak warranty**.

Deck mounted flashing




Shingles/shakes - EDL

- Step flashing pieces interweave with roofing material for proper water drainage.
- Additional step pieces (ZZZ 200) are required for shakes and other thick roofing materials.




Tile roofing - EDW

- Patented sill flashing features pliable pleats that form to most types of tile.
- Side and head flashing pieces form a gutter to direct water away from the skylight.



Metal roofing - EDM

- Flashing pieces interlock with roofing material for a fast, weather-tight installation.
- Sill apron features pliable pleats that form to the roof.



Other flashing options available


- Copper cladding and flashing
- Combi applications
- Biepack flashing - Type ECB

Curb mounted flashing



Shingles/shakes - ECL

- Step flashing pieces interweave with roofing material for proper water drainage.
- Additional step pieces (ZZZ 200) are required for shakes and other thick roofing materials.



Tile roofing - ECW

- Patented sill flashing features pliable pleats that form to most types of tile.
- Side and head flashing pieces form a gutter to direct water away from the skylight.