

Description-Basement Walls

Basement currently has spray foam insulation on all exterior walls and in cavity between all floor joists and above sill plate. Walls 1, 2 and 4 will not be insulated. Construction of walls will be 2x4. A PT 2x4 plate will be anchored to slab floor and a KD top plate will be anchored to rafters. These walls will be dry walled with moisture resistant dry wall. No ~~insulation~~ insulation will be installed in the ceiling of these areas. Walls 4, 5, 6, 3 and 7 will be constructed in the same manner but will be insulated. Insulation will be battled R17 insulation. The area made up by these walls will receive R19 battled insulation in the ceiling. Ceiling will be left open (no dry-wall).