



Manufacturer's Rating Label

Serial No.	Q421430122	
Model No.	PROE40 2 RU92	
Manufacture Date.	17OCT2014	
Cap. U.S. Gals.	40	
Phase	1	1
Volts AC	240	208
Upper Element Watts	4500	3380
Lower Element Watts	4500	3380
Total Watts	4500	3380



LISTED
HOUSEHOLD STORAGE
TANK WATER HEATER
1989



MADE IN MEXICO

Rheem Sales Company, Inc.
Water Heating Division
Montgomery, Alabama 36117 USA



WARNING

ELECTRIC WATER HEATER

CAUTION

FOR SAFE INSTALLATION AND OPERATION - Follow the instructions in the Use and Care Manual provided. A replacement copy may be obtained by writing the manufacturer.

This appliance must be installed in accordance with the manufacturer's instructions, local codes, utility company requirements, and/or in the absence of local codes, the latest edition of the National Electrical Code.

FOR YOUR SAFETY - DO NOT store or use gasoline or other flammable vapors and liquids in the vicinity of this or any other appliance. Keep rags and other combustibles away.

CAUTION - Hotter water increases the risk of scald injury. See use and Care Manual for instructions before changing the temperature setting.

WARNING - Any thermostat setting above 125 °F may cause severe burns and consume energy unnecessarily.

Power supply must be shut off before removing access panels prior to adjusting thermostat(s) or resetting temperature limiting control.

CAUTION - Risk of electric shock. Connect branch circuit equipment grounding means to water heater. For detailed information refer to Use and Care Manual. USE COPPER CONDUCTORS ONLY.

Tank must be full of water before being energized to avoid damaging the heating element(s).

WATER LEAKAGE - Regardless of the material from which a water heater is constructed, it will at some time leak, due to the corrosive action of water. This water heater must not be located in an area where leakage will result in damage to adjacent area or lower floors. When such area cannot be avoided, it is recommended that a suitable catch pan, adequately drained, be installed under the water heater. See Use and Care Manual.

WARNING: California law requires that this water heater must be braced, anchored, or strapped to avoid falling or moving during an earthquake. See Use and Care Manual for information regarding correct installation procedures.

CALIFORNIA PROPOSITION 65 WARNING: This product contains chemicals known to the State of California to cause cancer, birth defects, or other reproductive harm.

WARNING: When a supplemental heat source is connected to the Certified Household Electric Storage Tank Water Heater, provision must be made to limit the heat source temperature not to exceed that of the water heater thermostat setting.

CAUTION: If the water heater has a pressure relief valve, it must be tested annually. Failure to test the pressure relief valve may result in tank failure.

! DANGER



Water temperature over 125 °F can cause serious burns or death from scalding. Children, elderly and others are at highest risk of being scalded. See instruction manual before setting temperature on water heater. Final water heater setting is shown on the label.