

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400



NOTICE OF VIOLATION AND ORDER TO CORRECT

June 21, 2017

Responsible Party 1: STREET TRACY 188 BOLTON ST PORTLAND , ME 04102		
Location 188 BOLTON ST	CBL 186A D016001	Inspection Date 5/19/2017
Inspector Michael Scherb	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 7/15/2017.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 80- ANNEX D.4 1-HOUR FIRE DOORS ASSEMBLIES REQ; Listings are provided for floor fire door assemblies that are installed in fire-rated floor-ceiling or roof-ceiling assemblies that have been tested in accordance with the methods described in NFPA 288. The listing indicates the fire-rated assembly and the hourly rating (3 hours, 2 hours, 1.5 hours, 1 hour, .75 hours) for which the door can be permitted to be used so that access to the space above the ceiling or to the floor above can be provided without adversely affecting the fire resistance rating of the entire assembly. The listing provides limitations on the maximum size of an individual door opening and the total area of all door openings permitted for each 100 square feet of floor or ceiling. All doors to units need to be fire rated and self closing. Door to garage is fire rated but not labled as such.	2-1-18
CITY OF PORTLAND RULES AND REGS- CHAPTER 4.6 LABEL UNIT DOORS; 4.6 Commercial suites shall be designated as approved by the FD. In single floor buildings letter designations shall be acceptable. 4.6.1 Residential units shall be designated using numericals. 4.6.2 The first numerical of each residential unit shall be the floor designation. 4.6.3 In single floor buildings the floor designation shall be omitted.	2-1-18
NFPA 101- 7.2.2.4.2 HANDRAILS ARE NOT CONTINOUS; Required guards and handrails shall continue for the full length of each flight of stairs. At turns of new stairs, inside handrails shall be continuous between flights at landings. No returns on handrails in common stairwells	2-1-18

Violation	Proposed Date of Completion
NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) Gas fired appliances in basement need to be sprinklered	2-1-18
NFPA 101- 7.1.3.2.1 60-MIN FIRE DOOR ASSEMBLIES REQ; The separation shall have a minimum 1-hour fire resistance rating where the exit connects three or fewer stories. All doors to units need to be fire rated and self closing. Door to garage is fire rated but not labled as such.	2-1-18
FINAL DATE OF COMPLETED VIOLATION(S)	___/___/___
FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)	___/___/___

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

6-24-17
Date

TRACY STREET
Responsible Party

Date

Responsible Party

SEEN AND AGREED

6-29-2017
Date

Muthaine Cochran For Fire Prevention
Fire Prevention Bureau