



UNITS AND CLASSETS  
FOR USE IN FIRE RESISTIVE DUCT ASSEMBLIES  
SEE UL FIRE RESISTANCE DIRECTORY  
0020

LISTED



DUCT INSULATION  
0020

LISTED



FIRESTOP SYSTEMS  
SEE ENTERIC DIRECTORY

LISTED



FIRESTOP SYSTEMS  
SEE ENTERIC DIRECTORY

## 1. Product Description

3M™ Fire Barrier Duct Wrap 615+ is a fire resistant wrap consisting of an inorganic fiber blanket encapsulated with a scrim-reinforced foil. The product is 1-1/2 in. thick, 6pcf density.<sup>1</sup> It is used to fire rate commercial kitchen grease ducts as well as ventilation ducts, and is a proven alternative to 1 or 2 hour fire resistant rated shaft enclosures. With its excellent insulating capabilities, low weight and thin profile, it is an ideal choice for a duct enclosure system. This non-asbestos wrap installs easily because of its high flexibility and strength.

### Features

- Two-layer wrap for grease ducts rated as a shaft alternative per ASTM E 2336
- Zero clearance to combustible throughout the entire enclosure system for congested spaces
- One-layer wrap for fire-resistant ventilation ducts per ISO 6944
- High flexibility for installation ease
- Foil encapsulated for blanket protection, less dust, and high wrap strength
- Widest range of penetration seal systems

## 2. Applications

Two-layer applications of 3M™ Fire Barrier Duct Wrap 615+ meet the criteria of ASTM E 2336 'Standard Test Methods for Fire Resistant Grease Duct Enclosure Systems'.

3M™ Fire Barrier Duct Wrap 615+ as single-layer fire resistant wrap application has passed the ISO 6944 'Fire Resistance Tests - Ventilation Ducts'.

3M™ Fire Barrier Duct Wrap 615+ is an ideal fire resistive enclosure for commercial kitchen grease ducts and ventilation air ducts. It is a proven performance alternative to a 1 or 2 hour fire resistant rated shaft enclosures and provides zero clearance to combustible construction throughout the entire enclosure system. 3M™ Fire Barrier Water Tight Sealant 1000 NS, 3M™ Fire Barrier Water Tight Sealant 1003 SL or 3M™ Fire Barrier Water Tight Sealant 2000+ Silicone Sealants is used in combination with 3M™ Fire Barrier Duct Wrap 615+ to firestop the duct when the duct penetrates fire rated floors and walls.

## 3. Availability

Unit	Size	Quantity	Weight
Roll	24 in. x 25 ft. (60.9 mm x 635 cm)	1	45 lbs. (20.4 kg)
Roll	48 in. x 25 ft. (121 cm x 635 cm)	1	90 lbs. (40.8 kg)

## 4. Typical Physical Properties

Blanket Color	Weight
White	0.9 lbs./ft. <sup>2</sup> (4.38 kg/m <sup>2</sup> )

<sup>1</sup> In accordance with the tolerances in ASTM C 892 Standard Specification for High-Temperature Fiber Blanket Thermal Insulation.