Inspections Division
Date: 08/26/16

WINDOW SCHEDULE

NUMBER	DESCRIPTION	ROUGH OPENING	NOTES:
	DOUBLE HUNG	5'-0"W x 3'-6" H	

OPENING HEADER SCHEDULE

SPAN	DESCRIPTION	JACK STUDS (NUMBER)	KING STUDS (NUMBER)
3FT	(2) 2x6's	(1) Stud	() Studs
4FT	(2) 2x6's	(1) Stud	(1) Studs
6FT	(2) 2x10's	(2) Stud	(2) Studs
8FT	(2) 2x10's	(2) Stud	(2) Studs

CODE REVIEW

MUBEC – MAINE UNIFORM BUILDING AND ENERGY CODE
2009 INTERNATIONAL RESIDENTIAL BUILDING CODE,
2009 INTERNATIONAL ENERGY CONSERVATION CODE

ENERGY CODE NOTES:
1. ALL JOINTS AND PENETRATIONS SHALL BE CAULKED, GASKETED, OR COVERED WITH MOISTURE VAPOR-PERMABLE WRAPPING MATERIAL.
2. COMPONENT R-VALUES & U-FACTORS SHALL BE LABELED AS CERTIFIED.
3. INSULATION SHALL BE INSTALLED ACCORDING TO MANUFACTURERS INSTRUCTIONS, AND IN A MANNER THAT ACHIEVES THE REQ'D R-VALUE.
4. RECESSED LIGHTING FIXTURES INSTALLED IN THE BUILDING ENVELOPE SHALL BE TYPE C RATED AS MEETING ASTM E283, AND SEALED OR CAULKED.

RESIDENTIAL SPECIFICATIONS:

FLOOR SYSTEM:
Exsiting 2x
Subfloor as Indicated

EXTERIOR WALLS:
2x Studs as Indicated
Sheathing as Indicated
Air Infiltration Wrap
Siding/Finish as Indicated

INTERIOR WALLS:
2x4 Studs @ 16"oc
½" Gypboard as Indicated

ROOF SYSTEM:
Rafters as Indicated
Sheathing as Indicated (⅝")
15# Underlayment
Ice & Water Shield at Eaves/Valleys

INSULATION:
Exterior Walls R-21
Attic Cap R-38
Frost Wall R-10

VENTILATION:
Soffit – 2"Contin. Strip
Circulation Vents Between Rafters

INTERIOR FINISHES:
½" Gypboard or As Indicated At Walls/Ceilings
Flooring As Indicated
Paint/Stain As Indicated

Note: Items not Indicated Shall be Per Contract

STATE OF MAINE
BRUCE W. MACLEOD
No. 5422
LICENSED
PROFESSIONAL ENGINEER

DATE ISSUED 6/15/16

JASON LANDRY CONSULTING, LLC
17 NASON ROAD GORHAM, MAINE 04038 207-632-3111

DEBRA GEORGE
38 CALEB STREET
PORTLAND, MAINE

3
2
1

TITLE: NOTES

DATE: 5/20/16	DRAWN BY: JJL	DRAWING NUMBER:
SCALE: as noted	PROJ NO: 2016-030	S-4