

INTERIOR FIT-UP SCHEDULE

PDT Architects - 4/11/06

RM NO.	ROOM NAME	WALLS & DOOR FRAMES	FLOORING	BASE	CEILING	CEILING HEIGHT	CASEWORK	DOOR NO.	ROOM NAME	DOOR SIZE	DOOR HARDWARE	REMARKS
001	WAITING	PAINT	CARPET	WOOD BASE	GWB	10'-2"	NO CASEWORK	001	WAITING	EXISTING SUITE ENTRY DOOR	COORDINATE KEYING WITH TENANT	PROVIDE CHAIR RAIL - SEE OUTLINE SPEC; WINDOW "A" - 30"W X 56"H FIXED GLASS PANEL
002	CHECK-IN	PAINT	CARPET	WOOD BASE	GWB	8'6"	TRANSACTION COUNTER; REFER TO ATTACHED DOCUMENTS FOR DETAIL	002	CHECK-IN	NO DOOR		WINDOW "B" - +/-60"W X 56"H SLIDING GLASS WINDOW IN GWB OPENING; SEE OUTLINE SPEC.
003	RECEPTION	PAINT	CARPET	VINYL BASE	ACOUSTICAL CEILING TILE	8'-6"	PLAM WORK COUNTERS AS SHOWN ON PLAN; MOUNT AT 29" AFF	003	RECEPTION	NO DOOR		WINDOW "C" - 36"W X 48"H SLIDING GLASS WINDOW IN GWB OPENING; SEE OUTLINE SPEC. (FROSTED GLASS)
004	OFFICE	PAINT	CARPET	VINYL BASE	ACOUSTICAL CEILING TILE	8'-6"	WOOD TRANSACTION COUNTER; SEE PLANS AND OUTLINE SPEC.; PLAM WORK COUNTERS AS SHOWN ON PLAN; MOUNT AT 29" AFF	004	OFFICE	3'-0" X 7'-0" WITH HALF GLASS	LEVER LOCKSET	
005	WORK AREA	PAINT	CARPET	VINYL BASE	ACOUSTICAL CEILING TILE	10'-2"	PLAM WORK COUNTERS AS SHOWN ON PLAN; MOUNT AT 29" AFF; PROVIDE 2 WALL CABINETS, EACH 36"W X 30"H	005	WORK AREA	3'-0" X 7'-0" WITH FULL GLASS	LEVER LOCKSET	
006	CLOSET	PAINT	CARPET	VINYL BASE	ACOUSTICAL CEILING TILE	8'-0"	PROVIDE 5 ADJUSTABLE SHELVES, 14" DEEP	006 & 006A	CLOSET	(Two Sets) 3'-0" X 7'-0" 2-PANEL FLUSH BIFOLD DOOR	SEE OUTLINE SPEC.	
007	GYM	PAINT	CARPET	VINYL BASE	ACOUSTICAL CEILING TILE	10'-2"	WORK COUNTER: PLAM COUNTER MOUNTED 34" AFF; SINK CABINET: PROVIDE 36"W X 32.5"H SINK BASE CABINET; PROVIDE 36"W X 30"H WALL CABINETS ABOVE.	007	GYM	NO DOOR		
008	TREATMENT ROOM	PAINT	CARPET	VINYL BASE	ACOUSTICAL CEILING TILE	8'-0"	PROVIDE 36"W X 32.5"H (2 DOOR/ 2 DRAWER) BASE CABINET AND 36"W X 30"H WALL CABINET ABOVE	008	TREATMENT ROOM	3'-0" X 7'-0"	LEVER PASSAGE SET	PROVIDE GRAB BARS AND TOILET RM. ACCESSORIES PER ADA
009	CLIENT TOILET	PAINT	VCT	VINYL BASE	ACOUSTICAL CEILING TILE	8'-0"	NO CASEWORK	009	CLIENT TOILET	3'-0" X 7'-0"	LEVER PRIVACY SET	PROVIDE GRAB BARS AND TOILET RM. ACCESSORIES PER ADA
010	STAFF TOILET	PAINT	VCT	VINYL BASE	ACOUSTICAL CEILING TILE	8'-0"	NO CASEWORK	010	STAFF TOILET	3'-0" X 7'-0"	LEVER PRIVACY SET	

011	STAFF BREAK	PAINT	VCT	VINYL BASE	ACOUSTICAL CEILING TILE	10'-2"	<p>KITCHENETTE: PROVIDE 36"W X 32.5"H SINK BASE CABINET W/HANDICAP REMOVABLE FRONT AND 36"W X 32.5" W (2 DOOR/ 2 DRAWER) BASE CABINET; PROVIDE 72"W X 30"H WALL CABINETS ABOVE (4 DOORS); LAUNDRY AREA: PROVIDE 54"W X 32.5"H BASE CABINETS (3 DOORS/ 3 DRAWERS); PROVIDE 54"W X 30"H WALL CABINETS ABOVE (3 DOORS)</p>	011	STAFF BREAK	3'-0" X 7'-0" WITH NARROW LITE	LEVER PASSAGE SET	
-----	-------------	-------	-----	---------------	-------------------------------	--------	---	-----	-------------	--------------------------------------	----------------------	--