

FINISH SCHEDULE
PDT Architects - 3/28/06

RM NO.	NAME	WALLS				DOOR FRAMES	FLOOR	BASE	CLG	REMARKS
		N	E	S	W					
001	WAITING	P-1	P-3	P-1	P-1	P-1	CPT-1	WOOD	GWB	
002	CHECK-IN	P-1	P-1	P-3	P-1	P-2	CPT-1	WOOD	GWB	
003	RECEPTION	P-1	P-1	P-1	P-1	P-2	CPT-1	VB-1	ACT-1	PLAM-1 on counters
004	OFFICE	P-1	P-1	P-1	P-1	P-2	CPT-1	VB-1	ACT-1	PLAM-1 on counters
005	WORK AREA	P-1	P-1	P-1	P-1	P-2	CPT-1	VB-1	ACT-1	PLAM-1 on counters
006	CLOSET	P-1	P-1	P-1	P-1	NA	CPT-1	VB-1	ACT-1	
007	GYM	P-1	P-4	P-1	P-1	P-2 See Remarks	CPT-1	VB-1	ACT-1	At Doors #008,009,and 011, use P-4 on door frames; South wall at Client Toilet and Treatment Room shall be P-4; PLAM-1 at counters
008	TREATMENT ROOM	P-1	P-1	P-4	P-1	P-2	CPT-1	VB-1	ACT-1	PLAM-1 on counter
009	CLIENT TOILET	P-1	P-4	P-1	P-1	P-2	VCT-1	VB-2	ACT-1	
010	STAFF TOILET	P-1	P-1	P-1	P-4	P-2	VCT-1	VB-2	ACT-1	
011	STAFF BREAK	P-1	P-1	P-1	P-1	P-2	VCT-1/2 checker-board pattern	VB-2	ACT-1	PLAM-1 on counters
Notes:										
1.) Review locations of paint colors with architect before commencing work										
2.)										