ROOM FINISH SCHEDULE

NUMBER	ROOM NAME	FLOOR	BASE MATL	WALLS N	WALLS S	WALLS E	WALLS W	NOTES
01	Vestibule	CPT-1	RB	P-6	P-3	P-3	P-6	
02	Check-In	CPT-1	RB	P-1 / PLAM	P-1	P-1	P-1	
03	Reception	CPT-2	RB	P-1	P-1	P-1	P-1	
04	Waiting	CPT-2	RB	P-1,P-2,P-3	P-4	P-1,P-2,P-3	P-4, P-2, P-4	
05	Corridor	CPT-2	RB	P-1,P-2,P-3	P-1,P-2,P-3	P-1,P-2,P-3	P-4	
06	Change	CPT-2	RB	P-1	P-1,P-2,P-3	P-1	-	continue wood rail at South Wall only
07	Toilet Rm	RSF-1	RB	P-6	P-6	P-6	P-6	See Alternates for Ceramic Tile at wainscot & floor
08	Change	CPT-2		P-1,P-2,P-3	P-1	P-1	-	continue wood rail at North Wall only
09	Consult	CPT-2		P-1	P-1	P-1	P-1	
10	Screening Alcove	CPT-2		P-1,P-2,P-3	P-1,P-2,P-3	P-1,P-2,P-3	P-1,P-2,P-3	
11	Controlled Work Zone	CPT-2		P-5	P-5	P-5	P-5	
12	MRI Magnet Room	RSF-1		P-6	P-6	P-6	P-6	
13	MRI Equip			P-3	P-3	P-3	P-3	
14	Staff / Tech	CPT-2		P-5	P-5	P-5	P-5	
15	ExtremMRI	RSF-1		P-6	P-6	P-6	P-6	
16	ExtremMRI Equip			P-3	P-3	P-3	P-3	
18	Office	CPT-2		tbd-per Tammy	P-1	P-1	P-1	
19	Exam Pod							Match existing where work area required touch-up
20	Corridor							Match existing where work area required touch-up
21	Corridor							Match existing where work area required touch-up
23	Room							

NOTE: REFER TO OUTLINE SPECIFICATION FOR SELECTED FINISHES

DOOR AND FRAME SCHEDULE

DOOR NO.	TYPE	WIDTH	HT	FRAME TYPE	FRAME MTL	FIRE RATED	NOTES
02	4A	3' - 6"	7' - 0"	A1	ALUM		
03	2A	2A	7' - 0"		WD		
05	5A			A1	HM		SEE DOOR TYPE
07	1A	3' - 0"	7' - 0"	A1	HM		
09	2A	2A	7' - 0"		WD		
10	3A	4' - 0"	7' - 0"	A1	HM		HDWRE: PUSH-PULL & CLOSER
12	1A	4' - 0"	7' - 0"	A1	-		DOOR PROVIDED BY SHEILDING MANUFACTURER
12A	6A			6A	WD		
13	1A	3' - 8"	7' - 0"	A1	HM	45 MIN.	SOUND GASKETING & INSULATION FILLED FRAME
14	1A	3' - 0"	7' - 0"	A1	HM	45 MIN.	SOUND GASKETING & INSULATION FILLED FRAME
15	1A	3' - 6"	7' - 0"	A1	-		DOOR PROVIDED BY SHEILDING MANUFACTURER
16	1A	3' - 0"	7' - 0"	A1	HM		
16	1A	3' - 0"	7' - 0"	A1	HM		
17	1A	3' - 0"	7' - 0"	A1	HM		
18	1A	3' - 0"	7' - 0"	A1	HM		
20	1A	3' - 8"	7' - 0"	A1	HM	45 MIN.	SOUND GASKETING & INSULATION FILLED FRAME

4 Detail 1
1 1/2" = 1'-0"

BORROWED LIGHTS SHALL BE CLEAR FINISH WHITE OAK 1X, WITH DETAIL TO MATCH EXISTING BUILDING STANDARD, INCLUDING GWB REVEAL ALL (4) SIDES.

1 Borrowed Light Frames
1/4" = 1'-0"

2 Door & Frame Types
1/4" = 1'-0"

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

COPYRIGHT
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/16/13
Planner: Benjamin Wallace

OA Centers for Orthopedics
33 Sewall Street, Portland Maine

REGISTERED ARCHITECT
DAVID C. WEBSTER
No. 923
STATE OF MAINE

JOB NO.
12126

DRWN. CHK
Checker

SCALE:
As indicated

ISSUE
BID & PERMIT SET
MARCH 8, 2013

TITLE
SCHEDULES AND DIAGRAMS

SHEET
A600