

Click Here to Return to
Bill of Material/Index

**NO
EXCUSES!**



Fire Alarm Documents

The FAD is the perfect fit to meet the demanding code requirements today. NFPA 72 10.18.2.2.1.8 states that a cabinet must be “prominently labeled ‘FIRE ALARM DOCUMENTS’.”

This durable 16 gauge steel enclosure with a solid piano hinge and key lock will keep all of your code required documents in one safe place. With a 2GB USB flash drive it stores your fire alarm software safely and securely eliminating the occurrences of the software not being on site when technicians arrive to service the system. Along with your fire alarm software you can store your test & inspection documents, service records, manuals & as built drawings for the system. Using a standard USB B connector it allows you to plug in with any standard USB printer cable to upload or download information.

The FAD is designed to hold critical manuals and documents with a durable steel sleeve. It has designated hooks to organize key rings and hold important business cards for easy access and reference. Inside the cover it has a organized note table that allows for documentation for passwords and other critical system information. The steel sleeve can be easily removed to hold a 1.5” three ring binder.

The innovation of a single gang cutout inside the box to implement the Infinity line products with conduit knockout access enables you to provide other system functions for test and inspection. See the complete Infinity product line from Space Age Electronics for single gang electrical product solutions.



Standard Features:

- Installed with a 2 gig digital flash drive with USB B connector
- 2 Key ring hooks to hold system keys
- Business card holder for key contacts
- Overall Dimensions are 12” x 13” tall and 2 ¼ deep
- 16 gauge steel box and cover for security
- Durable powercoat baked on finish other colors available
- Standard ¾” cat 30 key lock other lock assemblies available
- Solid stainless steel piano hinge
- Permanently screened white ink 1” high “Fire Alarm Documents”
- Legend sheet for passwords and system information



ISO 9001
REGISTERED
COMPANY



ACEBOX

Space Age Electronics, Inc.
www.1sae.com
800.486.1723 Toll Free
508.485.0966 Local
508.485.4740 Fax

