KEYED NOTES

1. CAP EXISTING DUCTWORK.
2. RELOCATE EXISTING 6"DIA SUPPLY DIFFUSER
3. RELOCATE EXISTING 8"DIA SUPPLY DIFFUSER
4. RELOCATE EXISTING 8x6 GRILLE.

GENERAL NOTE:

IT IS THE INTENT OF THIS PROJECT THAT RTU-1 NOT ONLY SERVES THE NEW OR SUITE BUT ALSO PICK UP THE EXISTING OR SUITE. REPLACING EXISTING AHU-1,2 & 3 UNITS. SIMILARLY RTU-2, IN ADDITION TO PROVIDING COVERAGE AT THE NEW EXAM SUITE, PICK UP THE EXISTING NORTHWEST EXAM POD, REPLACING EXISTING AHU-4 UNIT. THE CONTRACTOR SHALL PHASE THE WORK SUCH THAT THE NEW SUITES ARE FUNCTIONING PRIOR TO COMPLETING THE TIE IN FOR EXISTING SUITES, TO MINIMIZE FACILITY DISRUPTION. NEW UNITS SHALL OPERATE AT REDUCED CAPACITY UNTIL FINAL TIE-INS ARE COMPLETE. COORDINATE WORK IN EXISTING AREAS STRICTLY WITH THE OWNER. ONCE FINAL TIE-INS ARE COMPLETE AND SYSTEM BALANCED, REMOVE EXISTING AHU-1,2,3 &4 COMPLETE AND CAP PIPES AND DUCTS AT MAINS REMOVING UNUSED BRANCHES UNLESS OTHER WISE DICTATED BY OWNER.

PLAN NORTH

TRUE NORTH

No.	DATE	DESCRIPTION
5	08-08-2013	ADDENDUM-5

REVISION SCHEDULE

A1 | MECHANICAL DUCTWORK ENLARGED AREA A PLAN - PHASE 2

1/4" = 1'-0"

8/8/2013 6:44:10 PM N:\Projects\2012\12064 ~ Eyecare Medical Group-Addition and Renovation\00 Drawing Files\12064_M.rvt

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 12/16/13

ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

Allied Engineering
Structural Mechanical Electrical Consultantsbeing
160 Veranda Street
Portland, Maine 04103
T: 207.321.2260
F: 207.321.2261
Web: www.allied-eng.com

ALLIED PROJECT No.: 12064
CAD FILE:

COPYRIGHT 2012
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

E.M.G. - PHASE 2 ADDITION & RENOVATION
53 Sewall Street, Portland, ME 04102

STATE OF MAINE ANTHONY S. DAVIS No. 8834 LICENSED PROFESSIONAL ENGINEER

PDT JOB NO. 12084

DRWN. CHK
Checker

SCALE: 1/4" = 1'-0"

ISSUE: JULY 11, 2013

TITLE
MECHANICAL DUCTWORK ENLARGED AREA A PLAN - PHASE 2

SHEET
MH100
ADDT