REFERENCE PLAN NOTES:

1. THE BASIS OF BEARING FOR THIS SURVEY WAS FROM THE LOCUS DEED REFERENCED IN NOTE 3.A.
2. DEED AND PLAN BOOK REFERENCES ARE TO THE CUMBERLAND COUNTY REGISTRY OF DEEDS.
3. RECORD OWNERSHIP OF THE PARCEL SURVEYED CAN BE FOUND IN THE FOLLOWING DEEDS:
   A. DEED FROM MMA BLAKE TO ROMAN CATHOLIC BISHOP OF PORTLAND DATED DECEMBER 28, 1967 AND RECORDED IN DEED BOOK 2734, PAGE 240.
   B. DEED FROM ALBERT KENISTON TO ROMAN CATHOLIC BISHOP OF PORTLAND DATED DECEMBER 22, 1952 AND RECORDED IN DEED BOOK 2734, PAGE 108.
   C. DEED FROM RICHARD KING TO ROMAN CATHOLIC BISHOP OF PORTLAND DATED DECEMBER 21, 1952 AND RECORDED IN DEED BOOK 2734, PAGE 111.
4. REFERENCE IS MADE TO THE FOLLOWING PLANS:
   A. BOUNDARY SURVEY / EXISTING CONDITIONS PLAN, 1340 CONGRESS STREET, PORTLAND, MAINE BY NORTHEAST CIVIL SOLUTIONS, INC., DATED JANUARY 12, 2006, NOT RECORDED.
   B. ALTA / ACSM LAND TITLE SURVEY OF ST. PATRICKS CHURCH BY PINKOTT SURVEY, INC., DATED JANUARY 18, 2013, NOT RECORDED.
5. THE PARCEL SURVEYED IS IDENTIFIED ON THE CITY OF PORTLAND TAX ASSESSOR'S MAP 191, BLOCK B, PARCEL 16 AND 17.
6. THE PARCEL SURVEYED IS LOCATED IN THE R-6 ZONE/DISTRICT. PORTIONS OF MAIN AND SPRUCE REQUIREMENTS ARE AS FOLLOWS:

FRONT YARD	25'
REAR YARD	25'
SIDE YARD	10'
MAXIMUM LOT COVERAGE	40%
MAXIMUM BUILDING HEIGHT	35'
PARKING (CHURCH)	1 SPACE / 3 FIXED SEATS

   FURTHER MUNICIPAL AND STATE OVERLAY ZONES MAY EXIST AND APPLY. BEFORE PROCEEDING ON ANY PROJECT, WE RECOMMEND VERIFYING THE CURRENT ZONING / SETBACKS / RESTRICTIONS WITH THE APPROPRIATE AGENCIES.
7. THE WIDTH AND LAYOUT OF LASSELL STREET AND CONGRESS STREET ARE AS FOLLOWS:
   A. LASSELL STREET – 60' AS SHOWN ON PLAN REFERENCED IN NOTE 4.A.
   B. CONGRESS STREET – WIDTH VARIES AS SHOWN ON PLAN REFERENCED IN NOTE 4.A.
8. REFERENCE IS MADE TO THE FOLLOWING EASEMENTS OF RECORD:
   A. 25' STRIP OF LAND AS NOTED IN DEED REFERENCED IN NOTE 3.A. BASED ON THE WORDING IN THE DOCUMENT, THAT THE EASEMENT DOES NOT RUN WITH THE PROPERTY, IT IS BELIEVED THAT SINCE PARCEL 191-B-25 IS NO LONGER OWNED BY MMA BLAKE THAT THE 25' EASEMENT HAS BEEN EXTINGUISHED.
   B. THE RIGHT AND EASEMENT TO CENTRAL MAINE POWER COMPANY AND NEW ENGLAND TELEPHONE & TELEGRAPH COMPANY, DATED JULY 22, 1940 TO CONSTRUCT, ERECT, REBUILD, OPERATE, MAINTAIN AND REMOVE ELECTRIC DISTRIBUTION LINES AS DESCRIBED IN DEED BOOK 2681, PAGE 118.
   C. AN AT-WILL LICENSE AGREEMENT BETWEEN CONGRESS REALTY ASSOCIATES AND THE CHURCH ALLOWING CHURCH EMPLOYEES TO PARK IN THE DESIGNATED SPACES ON THE CHURCH PROPERTY AS DESCRIBED IN A DOCUMENT DATED JULY 1, 2013, NOT RECORDED.

EROSION CONTROL NOTES:

1. INSTALL EROSION CONTROL BARRIERS AS SHOWN AS FIRST ORDER OF WORK.
2. SEE GENERAL EROSION CONTROL NOTES ON DETAIL SHEETS.
3. PROVIDE INLET PROTECTION AROUND ALL EXISTING AND PROPOSED CATCHBASIN INLETS WITHIN THE WORK LIMITS. MAINTAIN FOR THE DURATION OF THE PROJECT UNTIL PAVEMENT HAS BEEN INSTALLED.
4. INSTALL STABILIZED CONSTRUCTION ENTRANCES.
5. INSPECT INLET PROTECTION AND SILT FENCES DAILY AND AFTER EACH RAIN STORM OF 0.25 INCH OR GREATER. REPAIR/MODIFY PROTECTION AS NECESSARY TO MAXIMIZE EFFICIENCY OF FILTER. REPLACE ALL FILTERS WHICH SEDIMENT IS 1/3 THE FILTER HEIGHT.
6. CONSTRUCT EXCELSIOR MAT ON ALL SLOPES STEEPER THAN 3:1.
7. PRIOR TO ANY WORK ON SITE, DISTURBANCE COMMENCING ON THE SUBJECT PROPERTY, INCLUDING MOVING OF EARTH, THE APPLICANT SHALL INSTALL ALL EROSION AND SEDIMENTATION MITIGATION AND CONTROL MEASURES AS REQUIRED BY STATE AND LOCAL PERMITS AND APPROVALS.
8. CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST AND WIND EROSION THROUGHOUT THE CONSTRUCTION PERIOD. DUST CONTROL MEASURES SHALL INCLUDE, BUT NOT LIMITED TO, SPRINKLING WATER ON UNSTABLE SOILS SUBJECT TO ARID CONDITIONS.
9. ALL CATCHBASIN SUMPS AND PIPING SHALL BE THOROUGHLY CLEANED TO REMOVE ALL SEDIMENT AND DEBRIS AFTER THE PROJECT HAS BEEN PAVED.
10. TEMPORARY SOIL STOCKPILE SHALL BE SURROUNDED BY SILT FENCE AND SHALL BE STABILIZED BY TEMPORARY EROSION CONTROL MEDIANS. STOCKPILE AREAS TO BE LOCATED AS FAR AS POSSIBLE FROM THE DELINEATED EDGE OF WETLAND.
11. SAFETY FENCING SHALL BE PROVIDED AROUND STOCKPILES OVER 10 FT.
12. CONCRETE TRUCKS WILL BE REQUIRED TO WASH OUT (IF NECESSARY) SHOOTS ONLY WITHIN AREAS WHERE CONCRETE HAS BEEN PLACED. NO OTHER WASH OUT WILL BE ALLOWED.

DEMOLITION NOTES:

1. THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND THE LOCATIONS ARE NOT GUARANTEED BY THE OWNER OR THE ENGINEER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES, ANTICIPATE CONFLICTS, REPAIR EXISTING UTILITIES AND RELOCATE EXISTING UTILITIES REQUIRED TO COMPLETE THE WORK.
2. ALL MATERIALS SCHEDULED TO BE REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE SPECIFIED. THE CONTRACTOR SHALL DISPOSE OF ALL MATERIALS OFF-SITE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, ORDINANCES AND CODES.
3. COORDINATE REMOVAL, RELOCATION, DISPOSAL OR SALVAGE OF UTILITIES WITH THE OWNER AND APPROPRIATE UTILITY COMPANY.
4. ANY EXISTING WORK OR PROPERTY DAMAGED OR DISRUPTED BY CONSTRUCTION / DEMOLITION ACTIVITIES SHALL BE REPLACED OR REPAIRED TO MATCH ORIGINAL EXISTING CONDITIONS BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
5. THE CONTRACTOR SHALL NOTIFY LOCATION OF ALL EXISTING UTILITIES. CALL DIG SAFE AT LEAST 72 HOURS PRIOR TO THE COMMENCEMENT OF ANY DEMOLITION/CONSTRUCTION ACTIVITIES.
6. SAWCUT AND REMOVE PAVEMENT ONE FOOT OFF PROPOSED EDGE OF PAVEMENT OR EXISTING CURB LINE IN ALL AREAS WHERE PAVEMENT TO BE REMOVED ABUTS EXISTING PAVEMENT OR CONCRETE TO REMAIN.
7. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE THEMSELVES WITH THE CONDITIONS OF ALL OF THE PERMIT APPROVALS.
8. THE CONTRACTOR SHALL OBTAIN AND PAY FOR ADDITIONAL PERMITS, NOTICES AND FEES NECESSARY TO COMPLETE THE WORK AND ARRANGE FOR AND PAY FOR NECESSARY INSPECTIONS AND APPROVALS FROM THE AUTHORITIES HAVING JURISDICTION.
9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEMOLITION AND OFF-SITE DISPOSAL OF MATERIALS REQUIRED TO COMPLETE THE WORK, EXCEPT FOR WORK NOTED TO BE COMPLETED BY OTHERS.
10. UTILITIES SHALL BE TERMINATED AT THE MAIN LINE PER UTILITY COMPANY STANDARDS. THE CONTRACTOR SHALL REMOVE ALL ABANDONED UTILITIES LOCATED WITHIN THE LIMITS OF WORK. CONTRACTOR SHALL NOTIFY OWNER OF ALL DRAINS AND UTILITIES PRIOR TO REMOVAL/TERMINATION TO DETERMINE IF DRAIN OR UTILITY IS ACTIVE AND SERVICES ANY ON OR OFF-SITE STRUCTURE TO REMAIN. CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY SUCH UTILITY FOUND AND SHALL MAINTAIN THESE UTILITIES UNTIL PERMANENT SOLUTION IS IN PLACE.
11. PAVEMENT REMOVAL LIMITS ARE SHOWN FOR CONTRACTOR'S CONVENIENCE. ADDITIONAL PAVEMENT REMOVAL MAY BE REQUIRED DEPENDING ON THE CONTRACTOR'S OPERATION. CONTRACTOR TO VERIFY FULL LIMITS OF PAVEMENT REMOVAL PRIOR TO BID.
12. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL EXISTING STRUCTURES, CONCRETE PADS, UTILITIES AND PAVEMENT WITHIN THE WORK LIMITS SHOWN UNLESS SPECIFICALLY IDENTIFIED TO REMAIN. ITEMS TO BE REMOVED INCLUDE BUT ARE NOT LIMITED TO: CONCRETE, PAVEMENT, CURBS, LIGHTING, MANHOLES, UNDER GROUND PIPING, POLES, STAIRS, SIGNS, FENCES, RAMPS, BUILDING SLABS.
13. COORDINATE ALL WORK WITHIN THE PUBLIC RIGHT OF WAYS WITH THE CITY OF PORTLAND AND MAINE DEPARTMENT OF TRANSPORTATION.
14. REMOVE TREES AND BRUSH AS REQUIRED FOR COMPLETION OF WORK. CONTRACTOR SHALL GRUB AND REMOVE ALL STUMPS WITHIN LIMITS OF WORK AND DISPOSE OF OFF SITE IN ACCORDANCE WITH FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS.
15. CONTRACTOR SHALL PROTECT ALL PROPERTY MONUMENTATION THROUGHOUT DEMOLITION AND CONSTRUCTION OPERATIONS. SHOULD ANY MONUMENTATION BE DISTURBED BY BY THE CONTRACTOR, HE SHALL EMPLOY A LICENSED SURVEYOR TO REPLACE IT.
16. PROVIDE INLET PROTECTION BARRIERS AT ALL CATCH BASINS WITHIN CONSTRUCTION LIMITS AND MAINTAIN FOR THE DURATION OF THE PROJECT. INLET PROTECTION BARRIERS SHALL BE "HIGH FLOW SILT SACK" BY ACF ENVIRONMENTAL OR APPROVED EQUAL. INSPECT BARRIERS WEEKLY AND AFTER EACH RAIN OF 0.25 INCHES OR GREATER. CONTRACTOR SHALL COMPLETE A MAINTENANCE INSPECTION ON WORK OF TEN 9 THE FARING RECORDS CLOSED.
17. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF ANY CLEARING OR DEMOLITION ACTIVITIES.
18. THE CONTRACTOR SHALL PAY ALL COSTS NECESSARY FOR TEMPORARY PARTITIONING, BARRICADING, FENCING, SECURITY AND SAFETY DEVICES REQUIRED FOR THE MAINTENANCE OF A CLEAN AND SAFE CONSTRUCTION SITE.
19. SAWCUT AND REMOVE PAVEMENT AND CONSTRUCT PAVEMENT TRENCH PATCH FOR ALL UTILITIES TO BE REMOVED AND PROPOSED UTILITIES LOCATED IN EXISTING PAVEMENT AREAS TO REMAIN.
20. THE CONTRACTOR SHALL REMOVE AND SALVAGE EXISTING GRANITE CURB FOR REUSE.
21. UPON COMPLETION OF BUILDING DEMOLITION THE CONTRACTOR SHALL BACKFILL THE EXISTING BASEMENT AND FOUNDATION EXCAVATION. COORDINATE WITH THE GEOTECHNICAL ENGINEER FOR BUILDING FOUNDATION/BASEMENT BACKFILL MATERIAL REQUIREMENTS PRIOR TO BUILDING DEMOLITION.



LEGEND

- PROPERTY LINE
- ABUTTER LOT LINE
- BUILDING SETBACK
- APPROXIMATE EASEMENT LINE
- EDGE OF WETLAND
- APPROXIMATE LIMIT OF WORK (PHASE 1)
- EXISTING TREE LINE
- EXISTING FENCE
- EXISTING DRAINAGE
- EXISTING ELECTRIC/ TELEPHONE/CABLE
- EXISTING OVERHEAD WIRE
- EXISTING WATER
- EXISTING SEWER
- EXISTING GAS
- EXISTING CONTOUR
- EXISTING 10' CONTOUR
- EXISTING CONCRETE/BITUMINOUS SIDEWALK TO BE REMOVED
- ⌀5 REBAR WITH PLASTIC CAP STAMPED "NCE, INC. PLS 1340"(UNLESS NOTED OTHERWISE) SET ON DECEMBER 31, 2014
- FOUND IRON PIPE (SIZE & TYPE AS NOTED)
- FOUND MONUMENT (SIZE & TYPE AS NOTED)
- FOUND IRON ROD
- FOUND CAPPED IRON ROD (NUMBER AS NOTED)
- FOUND PK NAIL
- EXISTING SIGN
- EXISTING BOLLARD
- EXISTING TREE
- EXISTING LIGHT
- R/W — ROW ON FORMALLY OWNED BY
- 1234/567 — DEED BOOK AND PAGE (CCRD)
- TO BE REMOVED
- SILT FENCE

Tighe&Bond
Consulting Engineers
www.tighebond.com

STATE OF MAINE — Christopher M. Roy — 10170 — LICENSED PROFESSIONAL ENGINEER

Jewish Community Alliance of Southern Maine

Proposed Neighborhood Center

Portland, Maine

July 20, 2015

PROJECT NO.	
FILE:	JCOASMP1-CIVIL
DRAWN BY:	DWH
CHECKED:	MLM
APPROVED BY:	MLM

EXISTING CONDITIONS AND DEMOLITION PLAN - PHASE 1

SCALE: AS SHOWN

C-1A

M:\21\21-5152\civil\Plotting\JCOASMP1-ALT-EXISTING.dwg, Layout: EXHIBIT A, 7/20/2015 8:41:42 AM, dwhite, Tighe & Bond, Inc.