SEQUENCE OF OPERATION MATRIX

	Alarm Signal to C	Alarm Signal to B	Masterbox Annunciate	Activate Sp.	Activate Control Strobe Device	Activate Control P.	Shutdown System in Kitchen	E Supervisory Sign	- Trouble Signal to Central Station	Record Fund Contral Station via	System Inputs
System Inputs	Α	В	С	D	Е	F	G	Н	I	J	
Manual Pull Station	Х	Х	Х	Х	Х					Х	Manual Pull Station
Area Smoke Detector	х	х	х	х	х					х	Area Smoke Detector
Sprinkler Waterflow	х	х	х	x	х					х	Sprinkler Waterflow
Sprinkler Tamper Switch			х					х		х	Sprinkler Tamper Switch
Kitchen Ansul System	х	х	х	х	х					х	Kitchen Ansul System
Duct Smoke Detector			х				x	х		х	Duct Smoke Detector
Fire Alarm - AC Failure			х						х	х	Fire Alarm - AC Failure
Fire Alarm - Low Battery			х						х	х	Fire Alarm - Low Battery
Signal Line Open Circuit			х						х	х	Signal Line Open Circuit
Signal Line Ground Fault			х						х	х	Signal Line Ground Fault
Strobe Circuit Open			х						х	х	Strobe Circuit Open
Strobe Circuit Ground			х						х	х	Strobe Circuit Ground
Audio Circuit Open			х						х	х	Audio Circuit Open
Audio Circuit Ground			х						х	х	Audio Circuit Ground
System Ground Fault			х						Х	х	System Ground Fault
	Α	В	С	D	Е	F	G	Н	ı	J	