ROOM FINISH LEGEND

PT1	PAINT – TBD
PT2	PAINT – TBD
PT3	PAINT – TBD
PT4	PAINT – TBD
PT5	PAINT – TBD
PT6	PAINT – TBD
PT7	PAINT – TBD
FRP	FIBERGLASS REINFORCED PANELS
ACT1	ACOUSTICAL CEILING PANELS
ACT2	MOISTURE RETARDENT CEILING PANELS
VCT	VINYL COMPOSITION TILE – TBD
VB	VINYL BASE – TBD
EPX	EPOXY
CPT1	CARPET – TBD
CPT2	WALK–OFF MAT – TBD

Room Finish Schedule

ROOM NO	ROOM NAME	FLOOR	BASE	WALLS				CEILING		NOTES
				N	S	E	W	MATL	HEIGHT	
101	ENTRY	CPT/CPT2	VB	PT1	PT1	PT5	PT1	ACT1	8'–0"	CPT2 IS WALK–OFF/PEDIMAT 4'X10'
102	MEN	VCT	VB	PT1	PT1	PT1	PT4	ACT1	9'–0"	––
103	WOMEN	VCT	VB	PT1	PT1	PT1	PT4	ACT1	9'–0"	––
104	WAITING	CPT	VB	PT1	PT1	PT5	PT1	ACT1/GPDW	8'–6"	CLNG HT. VARIES – SEE A70.1
105	CORR.	CPT	VB	PT1	PT1	PT1	PT1	ACT1	8'–6"	––
106	INTERVIEW	VCT	VB	PT1	PT1	PT1	PT2	ACT	8'–0"	––
108	EXAM ROOM	VCT	VB	PT1	PT1	PT1	PT2	ACT1	8'–0"	––
109	EMG EXAM ROOM	VCT	VB	PT1	PT1	PT2	PT1	ACT	8'–0"	––
110	EXAM ROOM	VCT	VB	PT1	PT1	PT2	PT1	ACT	8'–0"	––
111	DR. HULL'S OFFICE	CPT	VB	PT1	PT1	PT3	PT1	ACT	8'–0"	––
112	STOR.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	8'–0"	––
113	N.P. OFFICE	CPT	VB	PT1	PT1	PT3	PT1	ACT	8'–0"	––
114	SPECIMEN TLT.	VCT	VB	PT1	PT4	PT1	PT1	ACT1	8'–0"	––
115	SOIL UTILITY	VCT	VB	PT1	PT1	PT2	PT1	ACT1	8'–0"	––
116	SUPPORT OFFICE	CPT	VB	PT1	PT3	PT1	PT1	ACT1	8'–0"	––
117	RECEPTION/ BUSINESS OFFICE	CPT	VB	PT1	PT1	PT3	PT1	ACT1	8'–0"	––
118	STOR.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	8'–0"	––
118	STAFF WOMEN	VCT	VB	PT4	PT1	PT1	PT1	ACT1	8'–0"	––
119	MEDICAL RECORDS	CPT	VB	PT1	PT1	PT3	PT1	ACT1	8'–0"	––
119	STAFF MEN	VCT	VB	PT4	PT1	PT1	PT1	ACT1	8'–0"	––
120	OPERATOR OFFICE	CPT	VB	PT1	PT3	PT1	PT1	ACT1	8'–0"	––
122	OFFICE SUPERVISOR	CPT	VB	PT1	PT3	PT1	PT1	ACT1	8'–0"	––
123	MECH.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	8'–0"	––
124	CORRIDOR	CPT	VB	PT1	PT1	PT1	PT1	ACT1	9'–0"	––
125	STAFF LOUNGE	VCT	VB	PT1	PT1	PT3	PT1	ACT1	8'–0"	––
126	JAN.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	8'–0"	––
127	REHAB SUPERVISOR	CPT	VB	PT1	PT1	PT1	PT3	ACT1	8'–0"	––
128	SOIL STOR.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	8'–0"	––
129	CORR.	CPT	VB	PT1	PT1	PT5	PT1	ACT1	8'–6"	––
130	TREATMENT	VCT	VB	PT1	PT1	PT2	PT1	ACT1	8'–0"	––
131	TREATMENT	VCT	VB	PT1	PT1	PT1	PT2	ACT1	8'–0"	––
132	TREATMENT	VCT	VB	PT1	PT1	PT2	PT1	ACT1	8'–0"	––
133	TREATMENT	VCT	VB	PT1	PT1	PT1	PT2	ACT1	8'–0"	––
134	TREATMENT	VCT	VB	PT1	PT1	PT2	PT1	ACT1	8'–0"	––
135	TREATMENT	VCT	VB	PT1	PT1	PT1	PT2	ACT1	8'–0"	––
136	TREATMENT	VCT	VB	PT1	PT1	PT2	PT1	ACT1	8'–0"	––
137	TREATMENT	VCT	VB	PT1	PT1	PT1	PT2	ACT1	8'–0"	––
138	TREATMENT	VCT	VB	PT1	PT1	PT2	PT1	ACT1	8'–0"	––
139	TREATMENT/OT	VCT	VB	PT1	PT1	PT2	PT1	ACT1	8'–0"	––
140	CORR.	CPT	VB	PT1	PT7	PT1	PT1	ACT1	8'–6"	––
141	STOR.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	9'–0"	––
142	FUNCTIONAL RESTORATION	RT	VB	PT1	PT7	PT7	PT1	PT	14'–0"	CLNG OPEN TO STRUCTURE ABOVE
143	CORR.	CPT	VB	––	PT1	PT7	PT1	ACT1	8'–6"	HANDRAIL @ EAST WALL
144	HOT/COLD PACK PREP	VCT	VB	PT1	PT1	PT1	PT1	ACT1	8'–0"	FLOOR DRAIN
145	CLEAN STOR.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	8'–0"	––
146	DOCUMENTATION	CPT	VB	PT1	PT1	PT	PT3	ACT1	8'–0"	––
147	GYM	RT	VB	PT1	PT7	PT7	PT1	PT	14'–0"	CLNG OPEN TO STRUCTURE ABOVE
148	STOR.	VCT	VB	PT1	PT1	PT1	PT1	ACT1	9'–0"	––
149	TREATMENT	VCT	VB	PT1	PT2	PT1	PT1	ACT	8'–0"	––
150	TREATMENT	VCT	VB	PT2	PT1	PT1	PT1	ACT	8'–0"	––
151	TREATMENT	VCT	VB	PT1	PT2	PT1	PT1	ACT	8'–0"	––
152	CORR.	CPT	VB	PT1	PT1	PT1	PT1	ACT1	9'–0"	––
153	WOMEN	VCT	VB	PT1	PT1	PT1	PT4	ACT1	8'–0"	––
154	MEN	VCT	VB	PT1	PT1	PT4	PT1	ACT1	8'–0"	––
155	SHOWER	EPX	EPX	FRP/PT1	FRP/PT1	FRP/PT1	FRP/PT1	ACT2	8'–0"	––
156	SHOWER	EPX	EPX	FRP/PT1	FRP/PT1	FRP/PT1	FRP/PT	ACT2	8'–0"	––
157	SHOWER	EPX	EPX	FRP/PT1	FRP/PT1	FRP/PT1	FRP/PT1	ACT2	8'–0"	––
158	LKRS	CPT	VB	PT1	PT2	PT	––	ACT1	8'–0"	––
159	SHOWER	EPX	EPX	FRP/PT1	FRP/PT1	FRP/PT1	FRP/PT1	ACT2	8'–0"	––
160	THERAPY POOL	EPX	EPX	FRP/PT1	FRP/PT1	FRP/PT1	FRP/PT7	ACT2	9'–0"	––
161	POOL EQUIP	EPX	EPX	FRP/PT1	FRP/PT1	FRP/PT1	FRP/PT1	ACT2	9'–0"	––
162	ELEC/TEL/ DATA	VCT	VB	PT1	PT1	PT1	PT1	ACT1	9'–0"	––
163	BILLING CODING	CPT	VB	PT1	PT3	PT1	PT1	ACT1	8'–0"	––
164	CONF. ROOM	CPT	VB	PT6	PT1	PT6	PT1	ACT1	8'–0"	––
165	ELEC	VCT	VB	PT1	PT1	PT1	PT1	ACT1	9'–0"	––
166	POOL STOR.	EPX	FRP	FRP/PT1	FRP/PT1	FRP/PT1	FRP/PT1	ACT2	9'–0"	––

ROOM FINISH SCHEDULE | NTS | REF: – | A1

HARRIMAN
Architects + Engineers
One Auburn Business Park
Auburn, Maine 04210
207.784.5100 tel
207.782.3017 fax
66 Pearl St., Suite 301
Portland, Maine 04101
207.775.0033 tel
207.775.0460 fax
www. harriman.com

© 2007

LICENSED ARCHITECT PATRICK SEAN AUSTIN No. 2028 STATE OF MAINE

Project Title

MERCY HEALTH CENTER
WESTGATE PLAZA
PORTLAND, MAINE

HA Project No. 07182

Key Plan

N

Mark	Date	Description
	07/01/08	ISSUED FOR PERMIT
	06/26/08	100% REVIEW SET

Issue Dates

Drawing Status

Drawing Title
ROOM FINISH SCHEDULE

PA / PE: PSC | Drawn By: JGJ

Drawing Number
A61.1