Inspections Division

Date: 05/13/14



EXISTING WINDOWS

PROPOSED CUT IN 28"X38"
PELLA SERIE 250 WINDOW
U FACTOR .27

DOUBLE 2X8 HEADER
WALLS ARE 2X4 CONSTRUCTION
NEW HEADER, KING STUDS & JACKS & SILLS
WALLS ARE SHEATHED W/ 3/4" BOARDS
AND VINYL SIDING

REMOVE 32" STORM DOOR AND
FRAME IN 32"X80" FIBERGLASS
ENTRY DOOR IN PLACE IN
SAME STRUCTURE

SCALE 1/4" = 1'