

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND BUILDING PERMIT

**This is to certify that**  
LATHAM LAURIE S

**Located at**  
118 COLONIAL RD

**PERMIT ID:** 2016-02214    **ISSUE DATE:** 09/21/2016    **CBL:** 192 K073001

has permission to **Renovations to bathroom and bedroom**  
provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Greg Gilbert

**Fire Official**

**Building Official**

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
THERE IS A PENALTY FOR REMOVING THIS CARD**

*Approved Property Use - Zoning*

*Building Inspections*

*Fire Department*

BUILDING PERMIT INSPECTION PROCEDURES  
Please call 874-8703 (ONLY)  
or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

**Check the Status or Schedule an Inspection On-Line at  
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases 6 months.**
- **If the inspection requirements are not followed as stated below, additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**

#### **REQUIRED INSPECTIONS:**

Electrical - Residential

Close-in Plumbing/Framing

Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

<b>City of Portland, Maine - Building or Use Permit</b>		<b>Permit No:</b> 2016-02214	<b>Date Applied For:</b> 08/18/2016	<b>CBL:</b> 192 K073001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
<b>Proposed Use:</b> Single Family	<b>Proposed Project Description:</b> Renovations to bathroom and bedroom			
<b>Dept:</b> Zoning <b>Status:</b> Approved <b>Reviewer:</b> Jennifer Thompson <b>Approval Date:</b> 09/06/2016		<b>Ok to Issue:</b> <input checked="" type="checkbox"/>		
<b>Note:</b>				
<b>Conditions:</b>				
<b>Dept:</b> Building Inspecti <b>Status:</b> Approved w/Conditions <b>Reviewer:</b> Greg Gilbert <b>Approval Date:</b> 09/19/2016		<b>Ok to Issue:</b> <input checked="" type="checkbox"/>		
<b>Note:</b>				
<b>Conditions:</b>				
<p>1) Fireblocking is required to provide a cut off of all concealed draft openings (both vertical and horizontal) in combustible construction, see Sec. R302.11.</p> <p>2) Bathrooms shall have a minimum ceiling height of 6 feet 8 inches at the center of the front clearance area for fixtures as shown in Figure R307.1. The ceiling height above fixtures shall be such that the fixture is capable of being used for its intended purpose. A shower or tub equipped with a showerhead shall have a minimum ceiling height of 6 feet 8 inches above a minimum area 30 inches by 30 inches at the showerhead.</p> <p>R307.2 Bathtub and shower spaces. Bathtub and shower floors and walls above bathtubs with installed shower heads and in shower compartments shall be finished with a nonabsorbent surface. Such wall surfaces shall extend to a height of not less than 6 feet (1829 mm) above the floor.</p> <p>The clear space in front of any water closet or bidet shall be not less than twenty-four (24) inches (610 mm).</p> <p>3) Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to bedrooms. That detection must be powered by both the electrical service (plug-in or hardwired) in the building and battery.</p> <p>Hardwired (non- ionization detection technology) interconnected battery backup smoke alarms shall be installed in each bedroom, protecting the bedrooms, and on every level.</p> <p>A field inspection will verify your current egress/ emergency escape, Smoke and Carbon Monoxide alarm arrangement and the City's minimal code requirements.</p> <p>4) Separate permits are required for any electrical: plumbing, sprinkler, fire alarm, HVAC systems, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.</p>				