

OWNER REVIEW

NAME	DATE

05.30.08 ISSUED FOR BID
NO. DATE DESCRIPTION
ISSUE LOG
△ = CLOUDED CHANGE

TD Banknorth
1410 Congress Street
Portland, ME 04102

PLUMBING
UNDERSLAB
PLAN

SCALE 1/4" = 1'-0"
DRAWN BY IGL
CHECKED BY
PROJ. ARCH. / ENGR. JR/IGL
PROJ. MGR. PJB
JOB NO. 07133.01
© SYMMES, MAINI & MCKEE ASSOCIATES, INC. 2008

P1.00

CONTAINMENT SOLUTIONS 3000 GALLON BELOW GROUND "FIBERGLASS" TANK WITH OPTIONAL 12"x12"x16" DEADMEN, HOLD DOWN STRAPS AND CLIPS TANK IS FURNISHED BY PLUMBING CONTRACTOR, INSTALLED BY SITE CONTRACTOR. COORDINATE BEDDING REQUIREMENTS WITH MANUFACTURER'S RECOMMENDATIONS. SITE CONTRACTOR RESPONSIBLE TO FURNISH BEDDING MATERIALS AND SET TANK IN PLACE. PLUMBING CONTRACTOR TO COORDINATE BULKHEAD TANK FITTINGS FOR STORM INLET, OVERFLOW OUTLET, NPCW INLET AND 36" MANHOLE ON TOP OF TANK WITH MANUFACTURER PRIOR TO TANK FABRICATION. P.C. TO PROVIDE EXTENSIONS ON MANHOLE TO SURFACE. BOTH TANK AND MANHOLE SHALL BE HEAVY DUTY TRAFFIC RATED.

