DOOR SCHEDULE

DOOR NO.	ROOM	DOOR SIZE	MATERIAL	TYPE	FRAME TYPE	MATERIAL	HDWR SET	NOTES
01	Entry Vestibule 100	(2) 3'-0"x 8'-0"	ALUM.	F	SF4	ALUM.	1	
02	Entry Vestibule 100	3'-0"x 8'-0"	ALUM.	F	SF8	ALUM.	2	
03	Entry Vestibule 100	3'-0"x 8'-0"	ALUM.	F	SF8	ALUM.	1A	
04	ATM Vestibule Sliding Storefront	6'-0"x 9'-6"	ALUM.		SF9	ALUM.	3	
05	PBR 1	3'-8"x 8'-8"	WD/GLASS	C	4	WD	14	
06	PBR 2	3'-8"x 8'-8"	WD/GLASS	C	4	WD	14	
07	PBR 3	3'-8"x 8'-8"	WD/GLASS	C	4	WD	14	
08	PBR 4	3'-8"x 8'-8"	WD/GLASS	C	4	WD	14	
09	PBR 5	3'-8"x 8'-8"	WD/GLASS	C	4	WD	14	
10	Toilet Women	3'-0"x 7'-0"	WD	A	1	WD	11	
11	Toilet Men	3'-0"x7'-0"	WD	A	1	WD	11	
12	Sprinkler Rm/Janitor	3'-0"x7'-0"	WD	A	3	HM	12	Paint door to match wall color
13	Copy/Fax to Employee Lounge	3'-0"x 7'-0"	WD	A	1	WD	4	
14	Mechanical Room	3'-0"x 7'-0"	WD	A	3	HM	12	Paint door to match wall color
15	Rear Egress	3'-0"x 7'-0"	INSUL.STL	E	SF6	ALUM.	9	Paint door- Color TBS
16	Tel/ Data Room	(2)2'-0"x 7'-0"	WD	C	2	WD		
17	Teller Area to Work Room	3'-0"x7'-0"	WD	A	1	WD	4	
18	Vault Vestibule to Work Room	3'-0"x7'-0"	WD	C	1	WD	4	
19	Coupon Room	3'-0"x 7'-0"	WD	A	1	WD	11	
20	ATM Service Room	(2)3'-0"x 7'-0"	WD	A	2	WD	12	
21	Lobby to Vault Vestibule	3'-0"x 8'-8"	WD	A	5	WD	4	
22	Cash Vault	3'-0"x 7'-0"	WD	A	1	WD	11	

GENERAL NOTE: See Specification Sections 08 41 13 and 08 71 00 for hardware sets.