



TYPICAL INTERIOR ELEVATIONS (scotch and amber scheme)

1/4" = 1'-0"



FLOOR FINISH PLAN

SCALE: 1/4" = 1'-0"

FINISHING SCHEDULE - SCOTCH & AMBER (U.S.)				
NO.	PRODUCT	MFG.	PATTERN & COLOR	SUPPLIER/CONTACT
1	PLASTIC LAMINATE	AS NOTED	BY STORE FIXTURE COMPANY	BY STORE FIXTURE COMPANY
2	PAINT (PUBLIC AREA WALLS, RESTROOMS)	BENJAMIN MOORE	BENJAMIN MOORE #HC-104-310, "SUSSEX GREEN"	BENJAMIN MOORE 4 COMPANY, CLEVELAND, OHIO. CONTACT: DOROTHY HAZINSKI. PHONE: (800) 635-5147, EXT. 1841.
3	PAINT (SERVICE AREA/MENU BOARD BULKHEAD)	BENJAMIN MOORE	BENJAMIN MOORE U.S. COLOR: #1054-310, "SHERWOOD TAN" CANADIAN COLOR: #CC-336-310, "WILD MUSHROOM"	BENJAMIN MOORE 4 COMPANY, CLEVELAND, OHIO. CONTACT: DOROTHY HAZINSKI. PHONE: (800) 635-5147, EXT. 1841.
4	NOT USED	----	----	----
5	NOT USED	----	----	----
6	HALL TILE (SERVICE AREA)	SAVOIA CANADA	COTTAGE SERIES: NEN SIENA (12" x 12") BY STONEPEAK. GROUT: MAPEI #11 SAHARA BEIGE, DESIGNER SERIES	STONEPEAK CERAMICS INC. TELEPHONE: (312) 506-2800
7	HALL TILE	SAVOIA CANADA	LE SPEZIE SERIES: CINNAMON (13" x 13") BY SAVOIA GROUT: MAPEI #41 IRISH CREAM, DESIGNER SERIES	SAVOIA CANADA LTD.-CUSTOMER SERVICE TELEPHONE ONTARIO: (416) 789-7778 TELEPHONE MONTREAL: (800) 572-8642.
8	NOT USED	----	----	----
9	CEILING TILE (PUBLIC AREA)	BPB (CELOTEX)	BPB (CELOTEX) #BET-154 24" x 24" REVEAL EDGE. COLOR: #090 SANDSTONE CEILING GRID: CELOTEX INTERMEDIATE DUTY, COLOR: "SANDSTONE"	BPB / CELOTEX CORPORATION (CEILING PRODUCTS DIVISION). CONTACT: BRIAN FITZGERALD (TO LOCATE LOCAL "AUTHORIZED" DEALER. TELEPHONE: (800) 235-6839.
10	PAINT (BULKHEAD PUBLIC AREA)	BENJAMIN MOORE	BENJAMIN MOORE #HC-37-310, "MYSTIC GOLD"	BENJAMIN MOORE 4 COMPANY, CLEVELAND, OHIO. CONTACT: DOROTHY HAZINSKI. PHONE: (800) 635-5147, EXT. 1841.
11	PAINT (EXTERIOR DOOR & FRAME)	BENJAMIN MOORE	PAINT "TDL EXTERIOR TAN" FINISH M22	1 COAT PRIMER 2 FINISH COATS BENJAMIN MOORE 4 COMPANY, CLEVELAND, OHIO. CONTACT: DOROTHY HAZINSKI. PHONE: (800) 635-5147, EXT. 1841.
12	NOT USED	----	----	----
13	NOT USED	----	----	----
14	PAINT (GWB CEILINGS)	BENJAMIN MOORE	SMOOTH PAINTED DRYHALL. BENJAMIN MOORE, REGAL AQUA VELVET #31901 PRIME W/ 201 LATEX SEAL.	BENJAMIN MOORE 4 COMPANY, CLEVELAND, OHIO. CONTACT: DOROTHY HAZINSKI. PHONE: (800) 635-5147, EXT. 1841.
15	LAMINATE DOORS	MARLITE	MARLITE HPL DOORS W/ WILSONART LAMINATE #1531-60 LIGHT BEIGE	CBC. CONTACT: JIM CAMPBELL. PHONE: (800) 444-4697, EXT. 8504
16	FLOOR & BASE TILE (PUBLIC AREA & RESTROOMS)	SAVOIA CANADA	COTTAGE SERIES: NEN SIENA (12" x 12") BY STONEPEAK. GROUT: MAPEI #47 CHARCOAL. BASE TILE CUT TO 6"X12" FOR PUBLIC AREA, RESTROOMS & HALL	STONEPEAK CERAMICS INC. TELEPHONE: (312) 506-2800
17	NOT USED	----	----	----
18	FLOOR TILE (RECEIVING & COOLER FLOOR)	STONEPEAK CERAMICS	NEW BASICS COLLECTION (12" x 12"), COLOR: TIM HORTON'S OATMEAL GROUT: BY MANUFACTURER	----
19	CEILING TILE (KITCHEN)	BPB (CAPAUL)	VINYLROCK X - VINYL FACED GYPSUM PANELS, 24" x 48". COLOR: WHITE GRID: CELOTEX INTERMEDIATE DUTY W/ ALUMINUM CAP COLOR: WHITE	BPB / CELOTEX CORPORATION (CEILING PRODUCTS DIVISION). CONTACT: BRIAN FITZGERALD (TO LOCATE LOCAL "AUTHORIZED" DEALER. TELEPHONE: (800) 235-6839.
20	VINYL FLOOR TILE (KITCHEN)	OLYMPIA	FLEXTILE: FT141 BY OLYMPIA. ADHESIVE: *FLEXTACH 300" BY FLEXTACT LTD.	OLYMPIA TILE, CUSTOMER SERVICE. TELEPHONE ONTARIO: (800) 667-8453 OR (416) 785-6666
21	TOILET PARTITIONS	HADRIAN MANUFACT. INC.	METAL FLOOR-MOUNTED AND OVERHEAD BRACED COLOR: TDL 2007	CONTACT: SCOTT JONES.CUSTOMER SERVICE (905) 333-0300
22	VINYL COVE BASE	OLYMPIA TILE	FLEXTILE 4" VINYLE COVE BASE COLOR: DARK BROWN	OLYMPIA TILE, CUSTOMER SERVICE. TELEPHONE ONTARIO: (800) 667-8453 OR (416) 785-6666
23	FRP PANELS (FOOD PREP AREA, RESTROOMS)	MARLITE CORPORATION	WALL PANELS, PEBBLED FINISH (0.092"), CLASS "C", COLOR: "TDL WHITE" PANELS & TRIM. PANEL SIZE: 4'x8' W/ MATCHING HOLDINGS.	MARLITE PRODUCTS, ATTN: BOB WHITMAN TELEPHONE (330) 343-6621
24	CEILING TILE (SERVICE AREA)	BPB (CAPAUL)	VINYLROCK X - VINYL FACED GYPSUM PANELS, 24" x 24". COLOR: SANDSTONE GRID: CELOTEX INTERMEDIATE DUTY, COLOR: "SANDSTONE"	BPB / CELOTEX CORPORATION (CEILING PRODUCTS DIVISION). CONTACT: BRIAN FITZGERALD (TO LOCATE LOCAL "AUTHORIZED" DEALER. TELEPHONE: (800) 235-6839.
25	PAINT (PTLON SIGN POST)	BENJAMIN MOORE	COLOR: "TDL PYLON YELLOW"	BENJAMIN MOORE 4 COMPANY, CLEVELAND, OHIO. CONTACT: DOROTHY HAZINSKI. PHONE: (800) 635-5147, EXT. 1841.
26	NOT USED	----	----	----
27	NOT USED	----	----	----

CODED NOTES

1 WAINSCOTING BY STORE FIXTURE COMPANY.

2 SERVICE AREA BULKHEAD IS ON THE SAME PLANE AS WALL WITH NO DEFINED EDGE - WALL TO BE THE SAME COLOR AS BULKHEAD - USE BULKHEAD PAINT COLOR.

3 SERVICE AREA BULKHEAD RUNS INTO WALL AT DIFFERENT PLANE WITH DEFINED EDGE - WALL TO BE THE DIFFERENT COLOR THAN BULKHEAD - USE WALL SPEC PAINT COLOR.

FLOOR TILE LEGEND

20 12"x12"x1/8" VINYL FLOOR TILE

16 12"x12" CERAMIC FLOOR TILE (FIELD)

18 12"x12" CERAMIC FLOOR TILE (FIELD)

NOTE: VERIFY FINAL FLOOR COVERING FINISHES W/ TIM HORTON'S.

NOTE: PAINT CEILING DIFFUSERS IN PUBLIC AREA / SERVICE AREA BENJAMIN MOORE #CC-336 "WILD MUSHROOM"

ROOM FINISH SCHEDULE - 1630-08 (U.S.) - Scotch & Amber															
NO.	ROOM	FLOORS		WALLS (NORTH IS REFERENCE)								CEILINGS		REMARKS	
		FIN.	BASE	NORTH		SOUTH		EAST		WEST		MAT'L.	FIN.		HEIGHT
100	VESTIBULE	16	16	GL	---	GL/GB	1 2	GL	---	GL/GB	1 2	GB	14	9'-7"	
101	PUBLIC AREA	16	16	MRPLY/GB	1 2	MRPLY/GB	1 2	MRPLY/GB	1 2	MRPLY/GB	1 2	SACT	9	9'-9"	APPLY 18 AT PUBLIC AREA SOFFIT, SEE SHEET A3.
102	OFFICE	20	22	PLY	23	PLY	23	PLY	23	PLY	23	GB	14	8'-0"	2X6 CEILING JOISTS
103	FREEZER	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	---	
106	MEN'S RESTROOM	16	16	MRGB/PLY	23 2	MRGB/PLY	23 2	MRGB/PLY	23 2	MRGB/PLY	23 2	GB	14	8'-0"	2X6 CEILING JOISTS
108	WOMEN'S RESTROOM	16	16	MRGB/PLY	23 2	MRGB/PLY	23 2	MRGB/PLY	23 2	MRGB/PLY	23 2	GB	14	8'-0"	2X6 CEILING JOISTS
107	HALL	16	16	GB	7	GB	7	GB	7	GB	7	SACT	9	9'-0"	
109	DRIVE-THRU	16	16	MRPLY/PLY	6	N/A	---	N/A	---	MRPLY/PLY	6	LGB	24	9'-4"	SEE INTERIOR ELEVATIONS
104	KITCHEN	20 18 W.L.	22 18 W.L.	MRPLY/PLY	23	MRPLY/PLY	23	MRPLY/PLY	23	MRPLY/PLY	23	GB	14	8'-4"	INSTALL 18 IN AREAS INDICATED ON PLAN
102	BEHIND COUNTER	16	16	MRPLY/PLY	6	N/A	---	MRPLY/PLY	6	N/A	---	LGB	24	9'-9"	APPLY 10 AT MENUBOARD BULKHEAD, SEE SHEET A3.
104	RECEIVING	20 18 W.L.	22 18 W.L.	MRPLY/PLY	23	MRPLY/PLY	23	MRPLY/PLY	23	MRPLY/PLY	23	GB	14	8'-4"	INSTALL 18 IN AREAS INDICATED ON PLAN
105	HOP	16	16	MRPLY/PLY	23	MRPLY/PLY	23	MRPLY/PLY	23	MRPLY/PLY	23	LGB	19	9'-9"	INSTALL 18 IN AREAS INDICATED ON PLAN
110	COOLER	18	18	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	MFG	---	
113	BREAK ROOM	20	22	PLY	23	PLY	23	PLY	23	PLY	23	GB	14	8'-4"	

MATERIAL/FINISH ABBREVIATIONS:

AL ALUMINUM
BR BRICK
FRGB FIRE-RESISTANT GYPSUM BOARD
GB GYPSUM BOARD

GL GLAZING
LGB LAY-IN GYPSUM BOARD
MFG MANUFACTURER FINISH/COMPONENT
MRGB MOISTURE-RESISTANT GYPSUM BOARD

MRPLY MOISTURE-RESISTANT PLYWOOD
PLY PLYWOOD
SACT SUSPENDED ACoustICAL CEILING TILE
W.L. WHERE INDICATED

C COVERED TILEBASE IN RESTROOM 4 ALL FOOD PREP / BOH AREA

REVISIONS:

Atlanta
Boston
Chicago
Dallas
Los Angeles
Miami
Sacramento

DATE ISSUED: 07-02-2008

wd partners

7007 Discovery Blvd
Dublin, OH 43017
Tel: 614.834.7777
Fax: 614.834.7777
wdpartners.com

Tim Hortons

1408 CONGRESS STREET
PORTLAND, ME 04102

**SCOTCH & AMBER SCHEME
FINISH SCHEDULE, TILE
ELEVATIONS & TILE PLAN**

DRAWN BY: DDS CHECKED BY: JPY

SAI # 08138

DRAWING NUMBER:
A10.1