



SHEET NOTES

- 01 1-HOUR SHAFT CONNECTING LESS THAN 4 STORIES. 2-HOUR RATED SHAFT TO BE PROVIDED AS BEST PRACTICE.
- 02 ATRIUM ENCLOSURE PER IBC 404.5 EXCEPTION 1
- 03 2-HOUR RATED SHAFT
- 04 3-HOUR FIRE RATED FIRE SHUTTER (NO EGRESS IN CLOSED POSITION)
- 05 2-HOUR RATED PARTITIONS AROUND ELECTRICAL ROOM. FIRE RATING NOT REQUIRED BY CODE, BUT RECOMMENDED AS BEST PRACTICE
- 06 2-HOUR RATED PARTITIONS ALONG ESCALATOR ENCLOSURE AND AT UNDERSIDE OF ESCALATOR, TYP.
- 07 2-HOUR RATED PARTITIONS AROUND ELEVATOR MACHINE ROOM
- 08 EXTERIOR WALLS OF VERTICAL EXIT ENCLOSURE, MINIMUM OF 10'-0" PER IBC 1019.14

Portland International Jetport
 1001 Westbrook Street
 Portland, Maine 04102

Gensler
 2020 K Street, Northwest
 Suite 200
 Washington DC 20006
 Telephone 202.721.5200
 Facsimile 202.872.8587

Date	Description
09/22/08	DESIGN DEVELOPMENT
12/03/08	75% CONSTRUCTION DOCUMENTS
01/23/09	95% CONSTRUCTION DOCUMENTS
10/26/09	ISSUED FOR PERMIT
2 11/12/09	ADDENDUM #2

GENERAL NOTES

- A IBC 302.3.1: NON SEPARATED USE: FIRE SEPARATIONS ARE NOT REQUIRED BETWEEN USES, EXCEPT AS REQUIRED BY OTHER PROVISIONS.
- B REFER TO A00.10 FOR OCCUPANT LOAD AND EGRESS REQUIREMENTS FOR DETAILED EGRESS CRITERIA
- C [Symbol] NOT IN CONTRACT (NIC)
- D [Symbol] 3-HOUR SPRAY-ON FIRE PROOFING ON UNDERSIDE OF SLAB ABOVE
- E [Symbol] EXIT STAIR LOCATION
- F [Symbol] 3-HR FIRE SEPARATION RATING
- G [Symbol] EXIT DISCHARGE
- H [Symbol] FCC, FHC, DFC (DEFIBRILLATOR) AND/OR SPC (STANDPIPE CONNECTION)

Seal/Signature

Project Name
PJM Terminal Enhancement

Project Number
09.6395.000

Description
EGRESS PLAN - LEVEL 3

Scale
As indicated

M:\09.6395.000\BIM\Building Model\User Model Files\Joyce Young_09.6395.000_PJM Jetport Expansion 00.rvt