

SHEET NOTES

- 01 EXISTING RELOCATED BELTA 4" TEL CONDUIT. SEE DEMOLITION PLAN E01.02.03.
- 02 EXISTING RELOCATED UNDERGROUND FEEDER FOR EXTERIOR LIGHTS. SEE DEMOLITION PLAN E01.02.03.
- 03 EXISTING RELOCATED FEEDER TO RELOCATED TSA PANEL. SEE DEMOLITION PLAN E01.02.03.
- 04 EXTEND EXIST 400A FEEDER CONDUCTORS FOR UNLITTED PANELBOARD TO NEW 400A JET BRIDGE DISCONNECT. SEE DEMOLITION PLAN E01.02.03. THIS IS A TEMPORARY ARRANGEMENT WHICH MUST BE DEMOLISHED AND REINSTALLED TO BE USED DURING CONSTRUCTION.
- 05 ROLL DOWN FIRE SHUTTER COORDINATE WITH CONNECTION POINT WITH VENDOR.
- 06 FAST ACTING OVERHEAD DOOR: PROVIDE FAST ACTING OVERHEAD DOOR WITH RECYCLED PAUL.
- 07 PROVIDE GFCI TYPE RECEPTACLE IN THE ESCALATOR LOWER LEVEL MACHINE ROOM. PROVIDE GFCI TYPE RECEPTACLE INSTALLATION WITH THE ESCALATOR CONTRACTOR.

Portland International
Jetport

1001 Westbrook Street
Portland, Maine 04102

2024 N. Street, NW
Suite 200
Washington, DC 20006
Telephone 202.271.5200
Facsimile 202.271.5297

Gensler
ASSOCIATES, INC.
Engineers • Architects • Planners • Construction Managers

