

SECTION 09680 - CARPET

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:

1. Tufted carpet.
2. Woven carpet.
3. Carpet cushion.

- B. Related Sections include the following:

1. Division 2 Section ["**Selective Demolition**"] ["**Selective Demolition for Interiors**"] for removing existing floor coverings.
2. Division 9 Section ["**Resilient Wall Base and Accessories**"] ["**Resilient Tile Flooring**"] for resilient wall base and accessories installed with carpet.
3. Division 9 Section "Carpet Tile."

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated. Include manufacturer's written data on physical characteristics, durability, and fade resistance. Include installation recommendations for each type of substrate required.

- B. Shop Drawings: Show the following:

1. Columns, doorways, enclosing walls or partitions, built-in cabinets, and locations where cutouts are required in carpet.
2. Existing flooring materials to be removed.
3. Existing flooring materials to remain.
4. Carpet type, color, and dye lot.
5. Locations where dye lot changes occur.
6. Seam locations, types, and methods.
7. Type of subfloor.
8. Type of installation.
9. Pattern type, repeat size, location, direction, and starting point.
10. Pile direction.
11. Type, color, and location of insets and borders.
12. Type, color, and location of edge, transition, and other accessory strips.

13. Transition details to other flooring materials.
 14. Type of cushion.
- C. Samples: For each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.
1. Carpet: **12-inch- (300-mm-)** square Sample.
 2. Exposed Edge Stripping and Accessory: **12-inch- (300-mm-)** long Samples.
 3. Carpet Cushion: **6-inch- (150-mm-)** square Sample.
 4. Carpet Seam: **6-inch (150-mm)** Sample.
 5. Mitered Carpet Border Seam: **12-inch- (300-mm-)** square Sample. Show carpet pattern alignment.
- D. Product Schedule: Use same room and product designations indicated on Drawings and in schedules.
- E. Maintenance Data: For carpet to include in maintenance manuals specified in Division 1. Include the following:
1. Methods for maintaining carpet, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
 2. Precautions for cleaning materials and methods that could be detrimental to carpet.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who is certified by the Floor Covering Installation Board or who can demonstrate compliance with its certification program requirements.
- B. Fire-Test-Response Characteristics: Provide products with the critical radiant flux classification indicated in Part 2, as determined by testing identical products per ASTM E 648 by an independent testing and inspecting agency acceptable to authorities having jurisdiction.
- C. Product Options: Products and manufacturers named in Part 2 establish requirements for product quality in terms of appearance, construction, and performance. Other manufacturers' products comparable in quality to named products and complying with requirements may be considered. Refer to Division 1 Section "Substitutions."
- D. Mockups: Before installing carpet, install mockups for each type of carpet installation required to demonstrate aesthetic effects and qualities of materials and execution. Install mockups to comply with the following requirements, using materials indicated for the completed Work:
1. Install mockups in the location and of the size indicated or, if not indicated, as directed by Architect.
 2. Notify Architect seven days in advance of dates and times when mockups will be installed.
 3. Demonstrate the proposed range of aesthetic effects and workmanship.
 4. Obtain Architect's approval of mockups before starting work.

5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
6. Remove mockups when directed.
7. Approved mockups may become part of the completed Work if undamaged at time of Substantial Completion.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. General: Comply with CRI 104, Section 5, "Storage and Handling."

1.6 PROJECT CONDITIONS

- A. General: Comply with CRI 104, Section 6.1, "Site Conditions; Temperature and Humidity."
- B. Environmental Limitations: Do not install carpet until wet work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.
- C. Do not install carpet over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended by carpet manufacturer.
- D. Where demountable partitions or other items are indicated for installation on top of carpet, install carpet before installing these items.

1.7 WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Special Carpet Warranty: Written warranty, signed by carpet manufacturer agreeing to replace carpet that does not comply with requirements or that fails within specified warranty period. Warranty does not include deterioration or failure of carpet due to unusual traffic, failure of substrate, vandalism, or abuse. Failures include, but are not limited to, more than 10 percent loss of face fiber, edge raveling, snags, runs, and delamination.
 1. Warranty Period: **[10]** <Insert number> years from date of Substantial Completion.
- C. Special Carpet Cushion Warranty: Written warranty, signed by carpet cushion manufacturer agreeing to replace carpet cushion that does not comply with requirements or that fails within specified warranty period. Warranty does not include deterioration or failure of carpet cushion due to unusual traffic, failure of substrate, vandalism, or abuse. Failure includes, but is not limited to, permanent indentation or compression.
 1. Warranty Period: **[10]** <Insert number> years from date of Substantial Completion.

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below, before installation begins, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
1. Carpet: Full-width rolls equal to 5 percent of amount installed for each type indicated, but not less than 10 sq. yd. (8.3 sq. m).

PART 2 - PRODUCTS

2.1 CARPET

- A. Available Product[s]: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
- B. Products: Subject to compliance with requirements, provide the following:
1. CPT-1: Milliken Remix 2.0 NO SUBSTITUTIONS
 - a. Color: As selected by Architect from manufacturer's full range.
 - b. Pattern: As selected by Architect from manufacturer's full range.
 - c. Source: Milliken Contract
Rob Roy, Senior Contract Manager
11 Arundel Rd
Raymond, ME
800-241-4826
Rob.roy@milliken.com
 2. CPT-2: Milliken Midnight Sparkle. NO SUBSTITUTIONS
 - a. Color: As selected by Architect from manufacturer's full range.
 - b. Pattern: As selected by Architect
 - c. Source: Reference Source above

2.2 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided by or recommended by the following:
1. Carpet manufacturer.
 2. Carpet cushion manufacturer.
- B. Adhesives: Water-resistant, mildew-resistant, nonstaining type to suit products and subfloor conditions indicated, that complies with flammability requirements for installed carpet and that is recommended by the following:

1. Carpet manufacturer.
 2. Carpet cushion manufacturer.
- C. Tackless Carpet Stripping: Water-resistant plywood in strips as required to match cushion thickness and that comply with CRI 104, Section 11.3.
- D. Seaming Cement: Hot-melt adhesive tape or similar product recommended by carpet manufacturer for taping seams and butting cut edges at backing to form secure seams and to prevent pile loss at seams.
- E. Metal Edge Strips: Extruded aluminum with mill finish of width shown, of height required to protect exposed edge of carpet, and of maximum lengths to minimize running joints.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet performance. Verify that substrates and conditions are satisfactory for carpet installation and comply with requirements specified.
- B. Concrete Subfloors: Verify that concrete slabs comply with ASTM F 710 and the following:
1. Slab substrates are dry and free of curing compounds, sealers, hardeners, and other materials that may interfere with adhesive bond. Determine adhesion and dryness characteristics by performing bond and moisture tests recommended by the following:
 - a. Carpet manufacturer.
 - b. Carpet cushion manufacturer.
 2. Subfloor finishes comply with requirements specified in Division 3 Section "Cast-in-Place Concrete" for slabs receiving carpet.
 3. Subfloors are free of cracks, ridges, depressions, scale, and foreign deposits.
- C. For wood subfloors, verify the following:
1. Underlayment over subfloor complies with requirements specified in Division 6 Section "Rough Carpentry."
 2. Underlayment surface is free of irregularities and substances that may interfere with adhesive bond or show through surface.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Comply with CRI 104, Section 6.2, "Site Conditions; Floor Preparation," and carpet manufacturer's written installation instructions for preparing substrates indicated to receive carpet installation.
- B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.
- C. Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents. Use mechanical methods recommended in writing by the following:
 - 1. Carpet manufacturer.
 - 2. Carpet cushion manufacturer.
- D. Broom and vacuum clean substrates to be covered immediately before installing carpet. After cleaning, examine substrates for moisture, alkaline salts, carbonation, or dust. Proceed with installation only after unsatisfactory conditions have been corrected.

3.3 INSTALLATION

- A. Direct-Glue-Down Installation: Comply with CRI 104, Section 8, "Direct Glue-Down Installation."
- B. Double-Glue-Down Installation: Comply with CRI 104, Section 9, "Double Glue-Down Installation."
- C. Carpet with Attached-Cushion Installation: Comply with CRI 104, Section 10, "Attached Cushion."
- D. Carpet with Preapplied Adhesive Installation: Comply with CRI 104, Section 10.4, "Pre-Applied Adhesive Systems (Peel and Stick)."
- E. Hook-and-Loop Installation: Comply with CRI 104, Section 10.5, "Hook and Loop Technology."
- F. Stretch-in Installation: Comply with CRI 104, Section 11, "Stretch-in Installation."
- G. Stair Installation: Comply with CRI 104, Section 12, "Carpet on Stairs."
- H. Comply with carpet manufacturer's written recommendations for seam locations and direction of carpet; maintain uniformity of carpet direction and lay of pile. At doorways, center seams under the door in closed position.
 - 1. Bevel adjoining border edges at seams with hand shears.
 - 2. Level adjoining border edges.
- I. Do not bridge building expansion joints with carpet.

- J. Cut and fit carpet to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet manufacturer.
- K. Extend carpet into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- L. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use nonpermanent, nonstaining marking device.
- M. Install pattern parallel to walls and borders.
- N. Install carpet cushion seams at 90-degree angle with carpet seams.

3.4 CLEANING AND PROTECTION

- A. Perform the following operations immediately after installing carpet:
 - 1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet manufacturer.
 - 2. Remove yarns that protrude from carpet surface.
 - 3. Vacuum carpet using commercial machine with face-beater element.
- B. Protect installed carpet to comply with CRI 104, Section 15, "Protection of Indoor Installations."
- C. Protect carpet against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet manufacturer.

END OF SECTION 09680