



F1 FLOOR DEMOLITION PLAN
D-1 1/8" = 1'-0"

NOT IN CONTRACT FOR INFORMATIONAL PURPOSES ONLY

REMOVAL KEY NOTES:

- 1 REMOVE WINDOWS COMPLETE. SAVE ONE FOR RE-INSTALLATION.
- 2 REMOVE OVERHEAD CANOPY. PLUG & GROUT HOLES AS REQUIRED.
- 3 REMOVE EXISTING SHELTER COMPLETE. REMOVE SLAB. DISCONNECT ALL POWER AT SOURCE & REMOVE ALL EXISTING UNDERGROUND WIRING.
- 4 REMOVE EXISTING HOT TOP TO CUT LINE.
- 5 REMOVE GAP FLASHING & OTHER ROOF-EDGE MATERIAL AS REQUIRED TO TIE NEW WORK INTO EXISTING.

GENERAL REMOVALS NOTES:

1. COORDINATE REMOVALS WITH EXISTING FINISHES TO REMAIN, AND WITH LOCATIONS OF NEW WORK.
2. PROTECT ALL EXISTING FINISHES, MATERIALS AND EQUIPMENT TO REMAIN. CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACEMENT OF ALL FINISHES, MATERIALS AND EQUIPMENT DAMAGED DURING CONSTRUCTION.
3. THE OWNER RESERVES THE RIGHT TO SAVE FOR FUTURE USE ALL SALVAGABLE ITEMS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL ITEMS NOT SAVED BY THE OWNER.
4. "REMOVE" MEANS TO REMOVE AND DISPOSE OF ITEMS.
5. CONTRACTOR SHALL BE RESPONSIBLE, AND SHALL PAY FOR, PROPER DISPOSAL OF ALL DEMOLITION & CONSTRUCTION DEBRIS.
6. DEMOLITION THAT HINDERS NORMAL JETPORT AND/OR PARKING OPERATIONS (INCLUDING, BUT NOT LIMITED TO CONSTRUCTION OF BARRICADE WALLS) MAY BE REQUIRED TO BE PERFORMED AT NIGHT. COORDINATE WITH OWNER.
7. REFERENCE ELECTRIC DRAWINGS FOR ELECTRICAL DEMOLITION & REMOVALS.
8. REFERENCE MECHANICAL DRAWINGS FOR MECHANICAL DEMOLITION & REMOVALS.
9. RESERVED

General Notes

ISSUED FOR CONSTRUCTION
4/18/2013



No.	Revision/Issue	Date

PWM
PORTLAND INTERNATIONAL AIRPORT
Facilities & Engineering
1001 Westbrook ST
Portland, ME 04102
207-874-8877

Project Name and Address
TAXI CAB WAITING ROOM AT PWM

Sheet Title
DEMOLITION PLAN

Project Number 13-103	Sheet D-1
Date Issued For Construction 4/18/2013	
Scale: Reference Individual Drawings	