

G-1 TAXI SHELTER FLOOR PLAN
 A-1 1/4" = 1'-0"

GENERAL BUILDING INFORMATION:

SQUARE FOOTAGE: 568 SF GROSS (502 NET)
 BUILDING HEIGHT: 12'-9"
 NUMBER OF FLOORS: 1 (ONE)
 CONSTRUCTION TYPE: III B

APPLICANT IDENTIFICATION INFORMATION:

APPLICANT NAME:
 CUTLER FACILITIES, AIA
 ASSISTANT FACILITIES MANAGER
 PORTLAND INTERNATIONAL AIRPORT
 1201 WESTBROOK STREET
 PORTLAND, ME 04102
 ARCHITECT NAME:
 SAME AS ABOVE

PROPOSED USE OF STRUCTURE:

OCCUPANCY CLASSIFICATION: IBC: BUSINESS
 NFPA: BUSINESS
 SQUARE FOOTAGE: 568 GROSS SF (502 NET)
 EXISTING STRUCTURE DOES NOT HAVE FIRE PROTECTION. THE SIZE OF THE BUILDING AND THE TYPE OF CONSTRUCTION MAKES IT NECESSARY THE PROPOSED ADDITION DOES NOT REQUIRE FIRE PROTECTION. THE SIZE OF THE ADDITION DOES NOT REQUIRE IT.
 SUPPRESSION SYSTEM:
 NOT APPLICABLE
 DETECTION SYSTEM:
 NOT APPLICABLE

LIFE SAFETY INFORMATION:

FIRE RESISTANCE RATINGS OF ALL MEANS OF EGRESS: 1 HOUR
 TRAVEL DISTANCE FROM MOST REMOTE POINT TO EXIT DISCHARGE: 68' (REFERENCE PLAN); MAXIMUM ALLOWABLE: 200'
 LOCATION OF ANY REQUIRED FIRE EXTINGUISHERS:
 FIRE EXTINGUISHER
 LOCATION OF EMERGENCY LIGHTING:
 2 HEADED EMERGENCY LIGHT
 LOCATION OF EXIT SIGNS:
 OUTDOOR DIAL LIGHTING HEAD
 LIT EXIT SIGN
 NFPA SUMMARY:


EGRESS NOTES:

MAXIMUM OCCUPANCY CAPACITY: 21
 TOTAL NUMBER OF MEANS OF EGRESS: 1
 MINIMUM REQUIRED EGRESS CAPACITY: 34"
 TOTAL DOOR EGRESS WIDTH: 34"
 MAXIMUM ALLOWABLE LENGTH OF TRAVEL: 200'
 MAXIMUM LENGTH OF TRAVEL: 68'



General Notes
ISSUED FOR PERMIT APPLICATION
 4/25/2003

No.	Revision/Issue	Date


 Facilities & Engineering
 1001 Westbrook St
 Portland, ME 04102
 207-874-8877

Project Name and Address
**TAXI CAB
 WAITING ROOM
 AT PWM**

Sheet Title
**FIRE
 DEPARTMENT
 REQUIREMENTS**

Project Number: 13-103	Sheet:
Date Issued For Construction: 4/19/2003	FD-1
Scale: Reference Individual Drawings	