

NOT FOR CONSTRUCTION

ARCHITECTURE 144 Fore Street P.O. Box 618
 Portland, Maine 04104
 ENGINEERING tel. (207) 772-3846
 PLANNING fax. (207) 772-1070
 INTERIORS www.smrtinc.com
 ENERGY
SMRT
 SMART PROJECT NO. 17033 PROJECT MGR. JCDRAWN AE OF RECORD
 DRG DRL CDS DJT


ISSUED FOR PERMIT
 DATE: 12/21/17
 BY: [Signature]
 STATUS: [Signature]
 THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICALS, INC. ALL SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICALS, INC.

SEBAGO
 TECHNICALS
 WWW.SEBAGOTECHNICALS.COM
 75 John Roberts Rd., Suite 1A 250 Goddard Rd., Suite B
 South Portland, ME 04086 Portland, ME 04106
 Tel. 207.200.2100 Tel. 207.783.6666
 PROJECT NO. FIELD BOOK DESIGN CHKD DRAWN

2ND FLOOR - SYSTEMS PLAN
 OF:
 PORTLAND INTERNATIONAL JETPORT
 VERTICAL CIRCULATION IMPROVEMENTS
 1001 WESTBROOK STREET
 PORTLAND, MAINE 04102

DATE 10-27-17 SCALE 1/8" = 1'-0"

2.EY102



2 RESTROOM SYSTEMS PLAN - 2ND FLOOR
 1/8" = 1'-0"

3 SYSTEMS PLAN - 2ND FLOOR
 1/8" = 1'-0"

KEYED NOTES:

- 1 PROVIDE DEDICATED PHONE LINE FOR EACH ELEVATOR. COORDINATE WITH OWNER FOR LOCATION TO GET PHONE WIRING FROM.
- 2 RELOCATE FIRE ALARM STROBE AND SPEAKER FROM LOCATION SHOWN ON 2.ED101 TO NEW LOCATION SHOWN. EXTEND EXISTING WIRING AS REQUIRED TO ACCOMMODATE NEW DEVICE LOCATIONS.

NOTES:

- 1. SEE SHEET 2.E-001 FOR LEGEND AND GENERAL NOTES.
- 2. EXTEND EXISTING SIMPLEX FIRE ALARM SYSTEM TO NEW INITIATING AND NOTIFICATION DEVICES SHOWN. PROVIDE ALL DEVICES, BACK BOXES, COMPLETE AND OPERABLE SYSTEM. ACTIVATION OF HEAT DETECTORS IN ELEVATOR PIT OR HOISTWAY TO DE-ENERGIZE SHUNT TRIP COIL FOR ELEVATOR CIRCUIT BREAKERS.

