

**SHEET NOTES**

**Portland International Jetport**  
 1001 Westbrook Street  
 Portland, Maine 04102

**Gensler**  
**oest ASSOCIATES, INC.**  
 343 Gorham Road, South Portland, ME 04106  
 engineers • architects • surveyors • construction managers

**amec**  
 343 Gorham Road, South Portland ME 04106  
 P: (207) 761-1770 F: (207) 774-1246 www.amec.com

Drainage Structure Schedule					
DESC.	RM	INV. IN	INV. IN	INV. IN	INV. OUT
A-69	57.31	49.74(24)	54.26(4)	49.74(16)	49.74(24)
A-70	58.53	51.08(18)	52.63(4)	51.48(15)	50.68(18)
A-71	57.60	-	-	-	51.60(15)
A-72-A	58.19	51.11(15)	51.06(4)	-	51.16(15)
A-73	58.16	51.16	-	-	51.01(18)
A-74	58.13	53.73	-	-	51.29
A-76	59.48	50.88	-	-	51.48
A-107A	57.94	53.94	53.24	-	53.14
A-107	58.57	53.35	53.35	-	53.55
A-108	61.93	56.15	54.30	-	54.30
A-109	61.82	54.50	54.64	-	54.37
A-110	63.57	56.97	-	-	56.67
A-111	63.50	-	-	-	57.99
A-112A	63.79	56.79	-	-	56.99
A-112	64.18	57.60	57.60	57.60	57.50
A-113	65.29	-	-	-	57.68
A-114	64.13	57.97	-	-	57.82
A-115	63.58	58.31	-	-	58.01
A-116	62.89	58.55	59.10(UD)	-	58.30
A-117	65.22	-	-	-	-
A-118	66.33	-	-	-	59.17
A-119	65.67	60.76	-	-	60.71
A-120	66.20	62.28	62.49	-	62.28
A-121	67.15	-	-	-	63.65
A-122	68.50	62.82	62.89	-	62.89
A-123	59.23	55.07	-	-	53.93
A-124	60.97	55.21	55.56	57.96(UD)	55.61
A-125	61.09	55.61	55.61	56.26(UD)	55.87
A-126	60.92	55.02	-	-	55.12
A-133	61.21	55.21	-	-	55.21
A-134	61.31	-	-	-	56.00
B-64A	70.71	67.03	66.53	67.63(2)	66.63
B-64	70.35	66.22	66.22	67.00(UD)	65.85
B-63	70.38	64.03	-	-	63.93
B-65	70.24	66.82	67.00(UD)	-	66.78
B-66	70.14	67.34(UD)	-	-	66.99
P-4	63.1	56.4(UD)	55.0	-	42.5
P-3	63.2	55.6	-	-	55.5
P-2	63.0	-	-	-	56.0
P-1	65.4	-	-	-	58.0
PC-5	63.08	57.43	-	-	57.38
W-CB-11	77.06	73.01(UD)	-	-	71.61
W-CB-12	77.01	71.05	73.75(UD)	-	71.01
W-CB-13	72.50	68.36	68.06(UD)	-	67.96
W-CB-14	72.49	68.56	68.56(UD)	-	68.56
W-WOU-4	73.56	-	-	-	68.43
W-DMH-3	81.40	-	-	-	-
W-CB-18	71.88	68.53	-	-	68.43

Sanitary Structure Schedule					
DESC.	RM	INV. IN	INV. IN	INV. IN	INV. OUT
SMH 23	76.33	65.66	-	-	65.63
SMH 24	?	?	FM ?	-	?
SMH 25	70.61	?	62.43 ?	-	?
SMH 26	70.25	61.75	-	-	61.80
SMH 27	65.00	?	-	-	55.02

THESE DRAWINGS ARE ISSUED FOR CONSTRUCTION AND REFLECT ALL AMEC ISSUED BULLETINS AND SKETCHES.

Issue	Date & Issue Description	By	Check
1	07/11/08	WJW	AWL
2	09/22/08	WJW	AWL
3	12/03/08	WJW	AWL
4	01/23/09	WJW	AWL
5	10/26/09	WJW	FEM
6	01-12-10	WJW	TM
7	02-05-10	WJW	MSD
8	4/23/10	WJW	TM
9	05/03/10	WJW	TM
10	09/01/11	WJW	SDH

**GENERAL NOTES**

- EXISTING CONDITIONS ARE BASED ON A TOPOGRAPHIC SURVEY BY GOOD DEEDS, INC., DATED JULY 2008. ADDITIONAL EXISTING CONDITIONS INFORMATION BASED ON TOPOGRAPHIC SURVEYS COMPLETED BY DUREN-CHEMERY / STANTEC DATED SPRING 2000, WINTER 2006, SUMMER 2007, EXISTING PHASE 1 PARKING GARAGE RECORD DRAWING, PHASE 2 PARKING GARAGE DESIGN DRAWINGS AND WESTERN EXPANSION DISK 8 AND 9 AS-BUILTS DATED 2006.
- ELEVATIONS ARE BASED UPON NGS BENCH MARK DISK, STAMPED 0121 1950, SET VERTICALLY IN THE EAST FACE OF THE CONCRETE FOUNDATION OF THE MAINTENANCE BUILDING, 0.7 FEET SOUTH OF THE NORTHEAST CORNER OF THE ORIGINAL BUILDING AND 1.5 FEET ABOVE GROUND. PUBLISHED ELEVATION IS 63.58 FEET NVD 1929.
- THE EXISTING FLAGPOLES AND SIGN LOCATED WEST OF THE EXISTING TERMINAL BUILDING SHALL BE REMOVED AND RELOCATED PER SITE LAYOUT PLAN 02.01.
- WITHIN THE CONSTRUCTION LIMIT LINES (CLL), THERE ARE VARIOUS EXISTING SITE ELEMENTS INCLUDING UTILITIES, WHICH MAY REQUIRE REMOVAL, REPLACEMENT OR RELOCATION AS A RESULT OF THE PROPOSED WORK OF THIS CONTRACT. IT IS INCUMBENT UPON THE CONTRACTOR TO REVIEW ALL CONTRACT DOCUMENTS INCLUDING REVIEW OF REFERENCE PLANS OF EXISTING FACILITIES AND FUTURE PHASES OF RELATED ADJACENT PROJECTS AVAILABLE FROM THE OWNERS TO CLEARLY UNDERSTAND AND DETERMINE THE INTENDED SCOPE OF WORK.
- ALL EXISTING PAVEMENT WITHIN THE CONSTRUCTION LIMITS REQUIRED TO BE REMOVED FOR CONSTRUCTION OF THIS PROJECT MAY BE TAKEN OFFSITE TO BE PROCESSED INTO RECLAIM BY SITE CONTRACTOR AND RE-USED AS RECLAIM GRAVEL IN THE BASE MATERIALS FOR EMPLOYEE PARKING AREAS. THE REUSE SHALL BE IN ACCORDANCE WITH MOST SPECIFICATIONS FOR RECLAIM MATERIAL AND APPROVED BY THE ENGINEER.
- ITEMS OUTSIDE CONSTRUCTION LIMIT LINE WILL BE REMOVED BY OTHERS UNDER A SEPARATE CONTRACT.
- THE REMOVAL OF ANY UTILITY SHALL NOT BEGIN PRIOR TO THE COORDINATION WITH EACH RESPECTIVE UTILITY OWNER.
- ALL EXISTING SITE SIGNAGE INCLUDING POSTS AND FOUNDATIONS WITHIN THE CONSTRUCTION LIMITS THAT WILL BE DISTURBED BY THE PROPOSED WORK SHALL BE REMOVED AND INVENTORY BY CONTRACTOR AND REINSTALLED AS SPECIFIED ON THE PLANS OR AS DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE.
- ALL EXISTING GRANITE CURBING REMOVED TO CONSTRUCT THIS PROJECT SHALL REMAIN THE PROPERTY OF THE CITY OF PORTLAND AND SHALL BE RESET AS DIRECTED BY THE OWNER OR THE OWNERS REPRESENTATIVE.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REMOVE AND LEGALLY DISPOSE OF ALL DEMOLITION MATERIALS, INCLUDING BUT NOT LIMITED TO, SITE LIGHTS AND BASES, PILING, PRECAST CONCRETE STRUCTURES, EXCAVATION, TREES AND BRUSH, GRUBBING, ETC., IN CONFORMANCE WITH ALL LOCAL, STATE AND FEDERAL REQUIREMENTS.
- THE CONTRACTOR SHALL NOT BEGIN DEMOLITION PRIOR TO IMPLEMENTATION OF TEMPORARY EROSION AND SEDIMENT CONTROL BMP'S AS SPECIFIED ON DRAWING C12.05 OF THE CONSTRUCTION DRAWINGS.
- QUANTITIES OF MATERIALS SHOWN TO BE REMOVED ARE APPROXIMATE ONLY. EXACT QUANTITIES REMOVED MAY VARY AND NO ADDITIONAL PAYMENT WILL BE MADE FOR ANY VARIANCE IN QUANTITIES SHOWN.
- REMOVE AND DISPOSE OF TREES AND VEGETATION DISTURBED BY WORK OF THIS PROJECT.

Project Name: P1W Terminal Enhancement  
 Project Number: 08-0395.000  
 CAD File Name: T:\5330101\SHEETS\C01.01.DWG  
 Description: EXISTING CONDITIONS PLAN  
 Scale: 1" = 40'  
 Date: 09/01/11  
 Ref. North

