

Key Banner - 13 oz

Features and Applications:

Key Banner is a white, opaque, front-lit banner. It is both tear and fade resistant, and is specially formulated to resist curling. Key Banner is available in both a matte and gloss finish. This smooth, scrim banner is weather resistant and printable with solvent and UV inks. Roll widths from 30" to 196" are available. Key Banner is listed on HP/Scitex's approved media list.

Specifications:

The following information on the physical and chemical characteristics of this product is based on tests believed to be reliable. The values are provided solely as a source of information. This information is given without a guarantee and does not establish a warranty. It is the responsibility of the purchaser/user to determine, prior to use, if this product is suitable for his/her use.

Properties	Test Method	Unit	Result
Transmittance	ASTM E 424 6.5.2	%	13.7
Tensile Strength	ISO 13934-1:1999 C.R.E. Cut Strip Method	KGF/5CM	L: 90.1 W: 89.3
Tearing Strength	ISO 13937-2:2000 C.R.E. Cut Strip Method	KGF	L: 7.1 W: 5.0
Elongation	ISO 13934-2:2000 C.R.E. Cut Strip Method	%	L: 14.9 W: 31.2
Adhesion Strength	ISO 2411.C.R.R	KGF/5CM	13.2
Flexing Endurance at Low Temp	DIN53351	Cycles	17000
Resistance to Low Temp	DIN53351		-20 degrees C
Resistance to High Temp	DIN53351		80 degrees C
Resistance to Weathering	ASTM G26, Xenon ARClamp, 18 min Spray/2 hr, 100 hr exp		No Change
Practice for operating light- exp, with and without water	ASTM G26, Method A, Type B Weather-O-Meter	Grade	4
Fire Resistant	Fire Test NFPA 701		Approved



GRIMCO

1585 Fencorp Dr • Fenton, Mo 63026

Ph: 800.542.9941 • Fax: 800.760.5575

www.grimco.com