1 FS.C.3 FUELING POSITION ELEVATION

SCALE: NOT TO SCALE

3 FS.C.2 FUELING ISLAND PLAN

SCALE: NOT TO SCALE

0 2' 4' 8'

2 FS.C.3 DISPENSER DETAIL

SCALE: NOT TO SCALE

4 FS.C.3 REINFORCING AT CANOPY COLUMN

SCALE: NOT TO SCALE

POSITIVE LIMITING BARRIER NOTES:

1) THE POSITIVE LIMITING BARRIER TO BE 5 CONTINUOUS "V" GROOVES 3/4" WIDE x 3/4" DEEP MIN. (1 1/4" DEEP MAX.), ON 4 3/4" CENTERS WITH CROSS INTERCONNECTING GROOVES, EQUALLY SPACED ON MIN. 12" MAX. 48" CENTERS.

2) GROOVES MUST BE KEPT CLEAN OF DIRT AND DEBRIS.

3) "V" GROOVES SHALL BE TROWELLED IN CONCRETE SLAB.

8 FS.C.3 POSITIVE LIMITING BARRIER DETAIL

SCALE: NOT TO SCALE

5 FS.C.3 EXPANSION JOINT DETAIL

SCALE: NOT TO SCALE

6 FS.C.3 SAWCUT DETAIL

SCALE: NOT TO SCALE

7 FS.C.3 CONCRETE FUELING APRON DETAIL

SCALE: NOT TO SCALE

ORIGINAL SHEET – ARCH D

Stantec

Stantec Cor
5 Dartmout
Auburn NH
03032–398
Tel. 603.66
Fax. 603.669.7636
www.stantec.com

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/31/13

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing – any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Consultants

Legend

Notes

STATE OF MAINE — JAMES E. STEWART No. 9848 — LICENSED PROFESSIONAL ENGINEER

9-27-13

Revision	By	Appd.	YY.MM.DD
ISSUE FOR PERMIT	JES	JES	13.09.27
ISSUE FOR BID	JES	JES	13.09.10
Issued	By	Appd.	YY.MM.DD

File Name: 02_191711186_FS.C.dwg	JSW	JKM/JSC	JSW	1–20–12
	Dwn.	Chkd.	Dsgn.	YY.MM.DD

Hertz

Client/Project
THE HERTZ CORPORATION

ABOVEGROUND STORAGE TANK INSTALLATION AND RELATED WORK
PORTLAND, ME

Title
ISLAND AND CANOPY ELEVATION

Project No. 191711186
Scale AS NOTED
Drawing No. FS.C.3
Sheet 8 of 19
Revision 0