PROPOSED USE GROUP A-3 GYMNASIUM
WITHOUT SPECTATORS

TOTAL SQUARE FOOTAGE
27,124 SQFT

AREA TO BE USED: 8,960 SQFT

CONSTRUCTION TYPE IIIB

MAX PROPOSED TEMPORARY OCCUPANCY = 49

EXISTING EXIT CAPACITY W DOOR MODIFICATIONS
14 LN .FT./ ,2" /PERSON =840

SCOPE OF WORK
1. POWER WASH SLAB
2. APPLY EPOXY TO ANY RUTS GREATER THAN ½" DEEP IN SLAB
3. IN RUTS<½" FLASH ANY TRIPPING EDGES
4. REMOVE ANY PROTRUDING METAL IN SLAB
5. ALL EXITS DOORS TO HAVE EXIT HARDWARE
6. ELECTRICAL WORK IS LIMITED TO LIFE SAFETY AND AREA LIGHTING AS INDICATED BELOW

NOTE; THERE IS NO MECHANICAL OR PLUMBING WORK

N

AREA TO BE USED BY CIRCUS (8,960 s.f) . INSTALL LIGHTING TO A LEVEL OF 10 fc /SF AT 3' aff
pROVIDE PHOTOMETRIC DATA WITH SHOP DRAWING

Prepared For:

Consultant:

Architect:
ARCHETYPE
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
THOMPSON'S POINT-BRICK SOUTH
THOMPSON'S POINT, PORTLAND ME

Revisions:

Scale: 3/32" = 1'-0"

Date: 9-2-2014

FIRST FLOOR PLAN

A1.01