



NOTE: SPRINKLERS EXISTING. LAYOUT SHALL BE ALTERED TO ACCOMODATE NEW ROOMS. NEW LAYOUT INVOLVES LESS THAN 20 HEADS SO ADDITIONAL PERMIT NOT REQUIRED. WORK SHALL BE PERFORMED BY RESIDENTIAL FIRE PROTECTION (SAME COMPANY THAT IS INSTALLING MAIN BUILDING SYSTEM AND HOLDS PERMIT FOR THIS WORK.

FE = FIRE EXTINGUISHER & SHALL BE TYPE ABC MOD # 5HI SA 40 ABC & MONITORED BY AAA FIRE.

NOTE: ALL EXTERIOR & TENANT DEMARCATION WALLS ARE EXISTING. ALL EXTERIOR DOORS & WINDOWS EXISTING

LEGEND

① RIGID SCREENS

FLOOR TO CEILING

30"

56"

6"

1/2" MDF PAINTED

3"x3" HARDWD VERTICAL

1"x3" HARDWD HORIZONTAL

DADO MDF PANEL INTO FRAME.

② 3'-0" X 6'-8" SOLID CORE DOORS (FIRE RATED DRS. w DOOR CLOSERS)

③ BI - FOLD DOORS (20" LEAVES)

④ 48"w x 96"h x 21"d DISPLAY CABINETS (PINE)

⑤ 26"w x 42"h x 18"d CUBBIES (PAINTED)

⑥ 2'-0" x 6'-8" x 1-3/8" SOLID CORE DOOR

E EXISTING DOORS

⊠ EXIS 8" SQ COLUMNS

▨ NEW 2X4 WALL W 5/8" GWB

▭ EXISTING WALLS

- - - MECH. RM WALL ABOVE

○ OVERHEAD VENT PIPE

DEKKO LLC

COLOR-ME-MINE

FLOOR PLAN

DATE: 9/12/14

SCALE: 3/16"=1'-0"

1

AS PER FIELD MEASUREMENTS 11/13/14