Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/17/16

MEZZANINE FRAMING PLANS

1/8"=1'-0"

DESIGN LIVE LOAD = 100 PSF UNLESS NOTED.

ALL BEARING WALLS ARE 2x4@16" UNLESS NOTED.

ALL HEADERS ARE (2)2x8 UNLESS NOTED.

JOISTS ARE CONTINUOUS OVER INTERIOR SUPPORTS EXCEPT WHERE NOTED.

SHEATHING IS 3/4" CDX PLYWOOD.

SEE ARCHITECTURAL FOR LOCATIONS AND EXTENTS OF ALL MEZZANINES.

FRAMING HARDWARE SCHEDULE	
LOCATION	CONNECTOR
6x6 POST BASE	ABU66 WITH 5/8"x6" TITEN HD SCREW ANCHOR
6x6 POST CAP AT MID'SPAN POSTS	CCQ4.62-5.55DS2.5
6x6 POST CAP AT END-SPAN POSTS	ECCQ4.62-5.55DS2.5
2x12 FLUSH-FRAMED JOIST	U210

ALL HARDWARE MANUFACTURED BY SIMPSON STRONGTIE OR APPROVED ALTERNATE.

TYPICAL JOIST AT BEARING WALL SECTION

1"=1'-0"

TYPICAL HANDRAIL SECTION

1"=1'-0"

STATE OF MAINE
DAVID TERRAULT
4840
PROFESSIONAL ENGINEER

Prepared For:

Consulting Engineer:
STRUCTURAL DESIGN CONSULTING
2696 Lake Shore Road
Unit 1-130
Gilford, NH
03249
Tel 603.293.8038

Architect:
ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
BRICK NORTH
BISSELL BROTHERS
Thopson's Point
Portland, Maine

Revisions:
Submitted for Permit 02/05/16

Scale: As Noted

Date: 05 FEB 16

MEZANINE FRAMING
PLANS AND DETAILS

S1.0