

SMOKE DETECTOR DUCT DETECTOR HEAT DETECTOR PULL STATION SPEAKER STROBE (XX NOTES CANDELA SETTING) STROBE (XX NOTES CANDELA SETTING) REMOTE TEST STATION ADDRESSABLE RELAY MODULE WIRE LEGEND

D 2 COND #16 AWG TWISTED SHIELDED FPL CABLE

DEVICE ADDRESSES:

IMPORTANT! DUPLICATE ADDRESSES BETWEEN DEVICES AND MODULES ARE NOT AN ERROR. EACH DEVICE MUST BE LABELED WITH THE LOOP AND SLC ADDRESS.

DEVICE EXAMPLE: L1D001 MODULE EXAMPLE: L1M001 NOTE: PULL STATIONS ARE IDENTIFIED AS MODULES BY THE FIRE

INSTALLATION NOTES:

FIELD WIRING SHALL BE INSTALLED FOLLOWING THE CURRENT EDITION OF NFPA 70: NATIONAL ELECTRIC CODE(2014), ALL APPLICABLE MUNICIPAL, COUNTY, & STATE CODES, REQUIREMENTS, AND REGULATIONS, AS WELL AS ALL MANUFACTURER GUIDELINES FOR INSTALLATION.

CONTROL PANELS, DEVICES, AND ALL OTHER SYSTEM COMPONENTS SHALL BE INSTALLED FOLLOWING THE CURRENT EDITION OF NFPA 72: NATIONAL FIRE ALARM AND SIGNALING CODE(2013), ALL APPLICABLE MUNICIPAL, COUNTY, & STATE CODES, REQUIREMENTS, AND REGULATIONS, AS WELL AS ALL MANUFACTURER **GUIDELINES FOR INSTALLATION.**

THE INSTALLER SHALL FOLLOW CORRECT CONDUCTOR POLARITY, INDICATED CIRCUIT DIVISIONS, PROPER GROUNDING AND SHIELDING WITHOUT EXCEPTION. IMPROPER INSTALLATION CAN RESULT IN INTERFERENCE, TRANSIENT VOLTAGE, OR SHORT CIRCUITS CAUSING UNDESIRED OPERATION OR DAMAGE TO THE CONTROL PANEL, DEVICES AND ANY OTHER INTEGRATED COMPONENTS.

THE GAUGE OF WIRE USED FOR THE SLC LOOP (IDENTIFIED AS "A" ON THIS PRINT), SHALL BE DETERMINED BY THE INSTALLER FOLLOWING GUIDELINES AND LIMITATIONS SET FORTH BY THE MANUFACTURER(NOTIFIER DOCUMENT #51253, INTELLIGENT CONTROL PANEL SLC WIRING MANUAL). THE SLC WIRING RISER IS SHOWN DIAGRAMMATICALLY ONLY TO ALLOW FOR VARIANCES IN ACTUAL WIRE DISTANCE, DEVICE PLACEMENT AND

ANY T-TAPPING OF SLC WIRING SHALL FOLLOW ALL REQUIREMENTS IN NOTIFIER DOCUMENT #51253, INTELLIGENT CONTROL PANEL SLC WIRING MANUAL.

WIRE FOR THE NOTIFICATION APPLIANCE CIRCUITS (IDENTIFIED AS "B" ON THIS PRINT), SHALL FOLLOW THE SPECIFIC REQUIREMENTS OF THE WIRING LEGEND.

HIS SYSTEM MEETS NEDA REALIDEMENTS FOR OPERATION AT 32,120°E AND A RELATIVE HUMIDITY OF 01-05% AT 87-93°F. HOWEVER, THE USEFUL LIFE OF THE SYSTEM'S STANDBY BATTERIES AND THE ELECTRONIC COMPONENTS MAY BE ADVERSELY AFFECTED BY EXTREME TEMPERATURE RANGES AND HUMIDITY. THEREFORE, IT IS RECOMMENDED THAT THIS SYSTEM AND ITS PERIPHERALS BE INSTALLED IN AN

ENVIRONMENT WITH A NORMAL ROOM TEMPERATURE OF 60-80°F. END OF LINE DEVICES MUST BE INSTALLED IN AN EASILY ACCESSIBLE LOCATION AND CLEARLY MARKED OR

DESIGN NOTES:

SYSTEM DESIGN PERFORMANCE AND COMPLIANCE WITH ALL APPLICABLE CODES AND REQUIREMENTS IS THE RESPONSIBILITY OF THE DESIGNING ENGINEER. PROPER INSTALLATION OF THIS SYSTEM AND ITS COMPONENTS IS THE RESPONSIBILITY OF THE INSTALLING CONTRACTOR. ANY ALTERATIONS, CHANGES, OR DEFICIENCIES MUST BE BROUGHT TO THE ATTENTION OF THE DESIGNING ENGINEER.

NORRIS INC. ASSUMES NO RESPONSIBILITY FOR ERRORS IN SYSTEM DESIGN OR INSTALLATION, AS WELL AS ANY COSTS ASSOCIATED WITH CORRECTING THESE ERRORS, IF ANY EXIST. UNLESS SYSTEM DESIGN OR INSTALLATION WAS PERFORMED BY NORRIS INC.

NOTIFICATION APPLIANCE CIRCUIT VOLTAGE DROPS								
Bissell Brothers Brewery								
Portland, Maine								
		WIRE		CURRENT	VOLTAGE	VOLTAGE	END	CIRCUIT
PANEL	CIRCUIT	GAUGE	LENGTH	DRAW	DROP	LOSS	VOLTAGE	LOAD
FCPS	NAC 1	14	108 FT	.58A	.32VDC	1.33%	23.68VDC	7%
FCPS	NAC 2	14	280 FT	1.054A	1.49VDC	6.21%	22.51VDC	13%
FCPS: 1.6A/8A Spare Capacity: 80%								
Calculated @ Maximum Distance/Current								

DATE: 04/13/2016

FA-1

PROJECT NAME	BY JRP		
BISSELL BROTHERS BREWERY THOMPSON'S POINT PORTLAND, MAINE 04101	СК		
	SCALE NONE SHEET		
MURRES INC			

2257 BROADWAY, SOUTH PORTLAND, MAINE