

PLUMBING FIXTURE CONNECTION SCHEDULE

TAG	DESCRIPTION	SAN	VENT	CW	HW
P-1	FLUSH VALVE WATER CLOSET	3"	2"	1/2"	-
P-2	URINAL	2"	1-1/2"	3/4"	-
P-3	LAVATORY	1-1/2"	1-1/2"	1/2"	1/2"
P-4	SHOWER	2"	1-1/2"	1/2"	1/2"
P-5	ADA SINGLE BOWL SS SINK	1-1/2"	1-1/2"	1/2"	1/2"
FD-1	FLOOR DRAIN	3"	2"	1/2" *	-
FS-1	12"x12" FLOOR SINK	3"	2"	1/2" *	-

MINIMUM SIZE OF BELOW SLAB SANITARY & VENT PIPING SHALL BE 2".
* - FLOOR DRAINS SHALL HAVE TRAP PRIMER CONNECTION SERVED BY ETP IN ATTIC.

PLUMBING SPECIFICATIONS

1. SANITARY (INCLUDING PROCESS WASTE) AND VENT PIPING SHALL BE SCHEDULE 40 PVC OR SERVICE WEIGHT CAST IRON. (VENT PIPING THROUGH ROOF SHALL BE CAST IRON (ONLY)
2. DOMESTIC WATER PIPING UNDER SLAB SHALL BE CROSSLINKED PEX.
3. FLOOR DRAINS SHALL INCLUDE TRAP PRIMER CONNECTION SERVED BY IN-LINE TRAP PRIMER INSTALLED ON NEAREST FIXTURE. TRAP PRIMER SHALL OPERATE ON A PRESSURE DROP OF 3-5 PSIG.
4. TRENCH DRAINS SHALL BE WATTS "DEAD LEVEL P" 6" WIDE PRE-SLOPED TRENCH DRAINS WITH REINFORCED STAINLESS STEEL SLOTTED GRATES.

NOTE - FIELD VERIFY LOCATIONS OF EXISTING UTILITY LOCATIONS

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/17/16

Prepared For:

Consultant: BENNETT ENGINEERING
MECHANICAL - ELECTRICAL
207.580.6945

Architect: ARCHETYPE
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project: BRICK NORTH EAST WING
THOMPSON'S POINT, PORTLAND ME

Revisions:
ISSUED FOR CONSTRUCTION

Scale: 1/8" = 1'-0"

Date: 11-30-15

UNDER SLAB PLUMBING PLAN

M2.01