



EVENT 9-10-2016
 OCCUPANCY 75

ASSEMBLY OCCUPANCY
 NO SPRINKLER
 EGRESS WIDTH - 75 (.2) = 15"
 2 DOORS REQUIRED WITH OCCUPANCY >50 (3 PROVIDED) IBC 1015.1
 COMMON PATH OF TRAVEL <75' IBC 1014.3
 EXIT ACCESS TRAVEL DISTANCE < 200' IBC TABLE 1016.1
 EXIT LIGHTING & SIGNS REQUIRED

PLUMBING CALC - UPC
 38 MEN, 38 WOMEN
 WOMEN - 3 TOILETS, 1 LAV
 MEN - 1 TOILET, 1 URINAL, 1 LAV