



EVENT ~~9/20/2016~~ **9/23/2016**
 OCCUPANCY ~~75~~ **125ppl**
 ASSEMBLY OCCUPANCY
 NO SPRINKLER
 EGRESS WIDTH - 75 (.2) = 15"
 2 DOORS REQUIRED WITH OCCUPANCY >50 IBC 1015.1
 (3 PROVIDED)
 COMMON PATH OF TRAVEL <75' IBC 1014.3
 EXIT ACCESS TRAVEL DISTANCE < 200' IBC TABLE 1016.1
 EXIT LIGHTING & SIGNS REQUIRED
 PLUMBING CALC - UPC
 38 MEN, 38 WOMEN
 WOMEN - 3 TOILETS, 1 LAV
 MEN - 1 TOILET, 1 URINAL, 1 LAV