

# *L.B. WHITE*

## *TS170ASPN220097*

### *DUCTABLE TENT PORTABLE GAS HEATER, 170,000 BTU*

- 
- Item: Ductable Tent Portable Gas Heater
  - Gas Type: LP
  - BtuH Output: 170,000
  - Min. Cylinder Size: 100 lb.
  - Heating Area: 4000 sq. ft.
  - Fuel Rate: 7.9 lb./hr.
  - Amps: AC5
  - Heater Voltage: 120VAC
  - Built-In Thermostat: Yes
  - Height: 32"
  - Width: 24-1/4"
  - Length: 32"
  - Air Flow: 1200 cfm
  - Hz60
  - Features: Ductable, Direct Fired, Enclosed Flame, Electronic Spark Ignition, Self Diagnostic Service Saver, Vent Mode for Simply Circulating Air
  - Safety Features: Enclosed Flame, Air Proving Switch, (2) High Limit Switches, Gas Control Valve and P.O.L. Valve

