



- IBC2009
- 311.3 USE GROUP S2 - LOW HAZARD STORAGE
- 1004.1.1 OCCUPANCY LOAD: AIRCRAFT HANGAR = 500sf GROSS PER PERSON
MEZZANINE = 990sf (OCCUPANCY LOAD = 2)
- 505.2 ALLOWABLE 1596 sf (1/3 of 4,788sf)
- 505.4-1 MEZZANINE CAN BE ENCLOSED
- 1015.1 SINGLE EGRESS (OCCUPANCY LOAD 2 < 29)
- 1014.3-2 COMMON PATH OF EGRESS TRAVEL = 100FT (OCCUPANCY LOAD 2 < 30)
- 1014.2-1 EGRESS NOT PROHIBITED THROUGH ADJOINING ROOM
- 1009.1-1 STAIR WIDTH 36"
- 1009.5 STAIR LANDING 36"

OWNER:
NEPTUNE PROPERTIES LLC
120 Exchange, Portland, Maine 04101
(207) 775-2100 Fax (207) 874-6988

ARCHETYPE, P.A.
ARCHITECTS
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Date	Scale
FEB 2, 2012	AS NOTED
Revisions:	Checked By:

PLANS
Project:
AIRPLANE HANGAR
MEZZANINE ADDITION
WESTBROOK STREET
PORTLAND, MAINE

A01