Date: 06/07/13
Building Inspection Division
Approved with Conditions

F1 DETAIL
3/4" = 1'-0"

TRUE NORTH
PLAN NORTH

E4 FOUNDATION PLAN
1/4" = 1'-0"

NOTES:
1. REFER TO ARCHITECTURAL DRAWINGS FOR ROOF SLOPE, WALL HEIGHT AND FINISHES.
2. COORDINATE FINAL DIMENSIONS WITH ARCHITECTURAL DRAWINGS

TRUE NORTH
PLAN NORTH

E8 ROOF FRAMING PLAN
1/4" = 1'-0"

D1 DETAIL
3/4" = 1'-0"

CORNER

NOTES:
1. VERTICAL REINF SHALL BE SOLID GROUTED.
2. FOR REINF SIZE, SEE NOTES.

INTERSECTION

JAMB AND WALL ENDS

C4 TYPICAL CMU REINFORCING DETAILS
3/4" = 1'-0"

WALL OPENING NOTES:

1. PROVIDE VERTICAL REINFORCING AT EACH SIDE OF EACH OPENING, WITHIN 16-INCHES OF ENDS OF WALLS, SEE DETAILS.
2. PROVIDE HORIZONTAL REINFORCING AT TOP AND BOTTOM OF WALL OPENINGS AND CONTINUOUSLY AT TOP OF WALLS, SEE DETAILS.
3. FILL CORES TO RECEIVE REINFORCING WITH 3000 PSI GROUT.
4. PROVIDE 48 BAR DIAMETER SPLICES IN MASONRY WALLS.
5. SEE MASONRY NOTES FOR REINFORCING NOT SHOWN.

A1 CMU, BOND BEAM, WALL OPENING AND END OF WALL REINFORCING
-

CORNER

INTERSECTION

A4 TYPICAL BOND BEAM REINFORCING DETAILS
3/4" = 1'-0"

A8 DETAIL
3/4" = 1'-0"

Project:

EMBASSY SUITES

1050 Westbrook Street
Portland, Maine 04102

Project Owner:

KTB Hospitality, LLC

1050 Westbrook St.
Portland, Maine 04102

BMA
Architectural Group
Professional Corporation
Architects ■ Designers ■ Planners
12 Middle Street
Amherst ■ New Hampshire ■ 03031
TEL 603 673 1991 FAX 603 672 1385
www.bmaworld.com

Seal:

Allied Engineering
Structural Mechanical Electrical Commissioning
160 Veranda Street
Portland, Maine 04103
T: 207.221.2260
F: 207.221.2266
Web: www.allied-eng.com

© COPYRIGHT 2013 ALLIED ENGINEERING, INC.

Allied Job Number:	13040
Cad File:	13040S.DWG

REVISIONS

1	06-06-13	CLOUDED AREAS

BMA Job Number:	2910
Drawn By:	PED
Checked By:	WPF
Phase:	PERMIT

Drawing Title:

STORAGE SHED

SHEET NUMBER:
SF-100
DATE: 24 MAY 2013

N:\Projects\2013\13040 ~ Embassy Suites ~ Portland-Me Shed Structure\00 Drawing Files\13040S.dwg Jun 06, 2013 - 8:19am