

---

**KRISTA BUTTERFIELD STONESCAPES**

---

May 15, 2016

Re: McCandless Property  
1247 Westbrook Street, Portland, Maine

Please see attached drawings with regard to the stone wall construction for the McCandless property. The final heights of all walls will be determined, to some degree, by final grade, but all walls will be built atop  $\frac{3}{4}$ " crushed stone base for 3' below final grade. This base material allows for movement and drainage and replaces the clay that was originally inhibiting correct filtration of surface water. In addition, and as somewhat of a redundancy, we will install 4" perforated drain pipe behind each of the walls as insurance against water settling behind or beneath construction.

Please do not hesitate to call or email with any questions.

Thank you,  
Krista Butterfield  
17 Melbourne St. B  
Portland, ME 04101  
(207) 450-4062  
kbstonescapes.com