

Location of Construction: 91 Whitney Ave		Owner: John & Martha Hebert		Phone:		Permit No: 970296	
Owner Address: 5AA Field, ME 04102		Lessee/Buyer's Name:		Phone:		Business Name:	
Contractor Name: WDEP		Address:		Phone:		Permit Issued: APR - 9 1997	
Past Use: 1-1am		Proposed Use: Same w/addition		COST OF WORK: \$ 7,500.00		PERMIT FEE: \$ 60.00	
Proposed Project Description: Construct Addition (14 x 26)		FIRE DEPT. <input type="checkbox"/> Approved <input type="checkbox"/> Denied		INSPECTION: Use Group: Type: 2		CITY OF PORTLAND	
		Signature:		Signature:		Zone: R-5 CBL: 186-C-023	
Permit Taken By: Mary Gresik		Date Applied For: 03 April 1997		PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.) Action: <input type="checkbox"/> Approved <input type="checkbox"/> Approved with Conditions <input type="checkbox"/> Denied		Zoning Approval: Special Zone or Reviews: <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan maj <input type="checkbox"/> minor <input type="checkbox"/> mm <input type="checkbox"/>	

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
2. Building permits do not include plumbing, septic or electrical work.
3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

**PERMIT ISSUED WITH REQUIREMENTS**

**CERTIFICATION**

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

SIGNATURE OF APPLICANT John Hebert		ADDRESS:		DATE: 03 April 1997		PHONE:	
RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE						PHONE:	

**Historic Preservation**  
 Not in District or Landmark  
 Does Not Require Review  
 Requires Review

**Action:**  
 Approved  
 Approved with Conditions  
 Denied

Date: 4/7/97

**CEO DISTRICT** 4

COMMENTS

4-19-97 Footings poured 2 parts & sides are keyed / Framing - 9' <sup>4</sup>/<sub>4</sub> x 16" / setbacks appear OK

4-22-97 - Core penetration to back fill / owners said drainage tile in + damp proofing on

5-2-97 - Back filling completed Anchor bolts OK / sill (PT) in progress  
 Appears Bulkhead elevation to High / for bulk head system? 44" wide x 10" high  
 Cut in poured wall @ top / OK

6-25-97 Inspected framing 2x4 walls checked window headers sheathing installed OK to close in party

5-19-98 T.E.K. Final inspection Ext. Deck Railings off and Smoke Det in Bed<sup>2nd</sup> 1<sup>st</sup> and Basement.

Inspection Record

Type	Date
Foundation: _____	_____
Framing: _____	_____
Plumbing: _____	_____
Final: <u>OK</u>	<u>5-19-98</u>
Other: _____	_____



Applicant: John Hebert  
Address: 91 Whitney Ave

Date: 4/7/17  
C-B-L: 186-C-23

**CHECK-LIST AGAINST ZONING ORDINANCE**

Date - Existing 1938 - to be main 1 family

Zone Location - R-5

Interior or corner lot -

Proposed Use/Work - 14' x 26' Addition

Sewage Disposal -

Lot Street Frontage -

Front Yard - 20' req - NA

Rear Yard - 20' req - 62' shown

Side Yard - 12' req - 21' shown

Projections -

Width of Lot -

Height - 2 story

Lot Area -

Lot Coverage/ Impervious Surface - 10,028 sq ft  
MAX 40% of lot coverage (4,011.2 sq ft MAX)

Area per Family -

Off-street Parking -

Loading Bays - N/A

Site Plan - N/A

Shoreland Zoning/ Stream Protection -

Flood Plains -

	4x8	= 32
	22x26	572
old	8x16	128
	3x13	39
<hr/>		
new	14x26'	364
		<u>1135</u>

## BUILDING PERMIT REPORT

DATE: 8 April 97 ADDRESS: 91 Whitney Ave.  
REASON FOR PERMIT: To Construct a 14'x26' addition.  
BUILDING OWNER: John & Martha Herbert  
CONTRACTOR: Owner  
PERMIT APPLICANT: ↑ APPROVAL: \*1, \*2, \*7, \*8, \*9, \*10, \*11, \*15, \*20, \*26 DENIED

### CONDITION(S) OF APPROVAL

1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
2. Before concrete for foundation is placed; approvals from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection)
3. Precaution must be taken to protect concrete from freezing.
4. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
5. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of ½ inch gypsum board or the equivalent applied to the garage means of ½ inch gypsum board or the equivalent applied to the garage side. (Chapter 4 Section 407.0 of the BOCA/1996)
6. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993) U.L. 103.
7. Guardrail & Handrails A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42" , except Use Group R which is 36". In occupancies in Use Group A, B, H-4, I-1, I-2 M and R and public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect.
8. Headroom in habitable space is a minimum of 7'6".
9. Stair construction in Use Group R-3 & R-4 is a minimum of 10" tread and 7 3/4" maximum rise. All other Use group minimum 11" tread. 7" maximum rise.
10. The minimum headroom in all parts of a stairway shall not be less than 80 inches.
11. Every sleeping room below the fourth story in buildings of use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension shall be 20 inches (508mm), and a minimum net clear opening of 5.7 sq. ft.
12. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units.
13. All vertical openings shall be enclosed with construction having a fire rating of at least one (1)hour, including fire doors with self closer's.
14. The boiler shall be protected by enclosing with (1) hour fire-rated construction including fire doors and ceiling, or by providing automatic extinguishment.
15. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 19, 920.3.2 (BOCA National Building Code/1996), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):
  - In the immediate vicinity of bedrooms
  - In all bedrooms
  - In each story within a dwelling unit, including basementsIn addition to the required AC primary power source, required smoke detectors in occupancies in Use Groups R-2, R-3 and I-1 shall receive power from a battery when the AC primary power source is interrupted. (Interconnection is required)

16. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type.
17. The Fire Alarm System shall be maintained to NFPA #72 Standard.
18. The Sprinkler System shall maintained to NFPA #13 Standard.
19. All exit signs, lights, and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023. & 1024. Of the City's building code. (The BOCA National Building Code/1996)
- X 20. All construction and demolition debris must be disposed at the City's authorized reclamation site. The fee rate is attached. Proof of such disposal must be furnished to the office of Inspection Services before final Certificate of Occupancy is issued or demolition permit is granted.
21. Section 25-135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".
22. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification to the Division of Inspection Services.
23. This permit does not excuse the applicant from obtaining any license which may be needed from the City Clerk's office.
24. Ventilation shall meet the requirements of Chapter 12 Sections 1210. of the City's Building Code.
25. All electrical and plumbing permits must be obtained by a Master Licensed holders of their trade.
26. Your plans shows 2x8@16" O.C. spanning 14' - 2x10@16" O.C. will be required for a 14' span
27. \_\_\_\_\_
28. \_\_\_\_\_

  
P. Samuel Hoffses, Chief of Code Enforcement

cc: Lt. McDougall, PFD  
Marge Schmuckal

# PLUMBING APPLICATION

## PROPERTY ADDRESS

Town Or Plantation: Portland  
 Street Subdivision Lot #: 91 Whitney Ave.

## PROPERTY OWNERS NAME

Last: Hebert First: John  
 Applicant Name: Same  
 Mailing Address of Owner/Applicant (If Different): Same

PERMIT # 4100 STATE COPY  
 Date Permit Issued: 7.7.97 \$ 12 FEE  If Double Fee Charged  
 L.P.I. # 0129  
 Local Plumbing Inspector Signature: \_\_\_\_\_

## Owner/Applicant Statement

I certify that the information submitted is correct to the best of my knowledge and understand that any falsification is reason for the Local Plumbing Inspector to deny a Permit.

Signature of Owner/Applicant: \_\_\_\_\_ Date: 7.7.97

## Caution: Inspection Required

I have inspected the installation authorized above and found it to be in compliance with the Maine Plumbing Rules.

Local Plumbing Inspector Signature: \_\_\_\_\_ Date Approved: \_\_\_\_\_

## PERMIT INFORMATION

This Application is for	Type Of Structure To Be Served:	Plumbing To Be Installed By:
1. <input checked="" type="checkbox"/> NEW PLUMBING 2. <input type="checkbox"/> RELOCATED PLUMBING	1. <input checked="" type="checkbox"/> SINGLE FAMILY DWELLING 2. <input type="checkbox"/> MODULAR OR MOBILE HOME 3. <input type="checkbox"/> MULTIPLE FAMILY DWELLING 4. <input type="checkbox"/> OTHER — SPECIFY _____	1. <input type="checkbox"/> MASTER PLUMBER 2. <input type="checkbox"/> OIL BURNERMAN 3. <input type="checkbox"/> MFG'D. HOUSING DEALER / MECHANIC 4. <input type="checkbox"/> PUBLIC UTILITY EMPLOYEE 5. <input checked="" type="checkbox"/> PROPERTY OWNER LICENSE # _____

Hook-Up & Piping Relocation Maximum of 1 Hook-Up	Column 2		Column 1	
	Number	Type of Fixture	Number	Type of Fixture
HOOK-UP: to public sewer in those cases where the connection is not regulated and inspected by the local Sanitary District.  <b>OR</b>  HOOK-UP: to an existing subsurface wastewater disposal system.		Hosebibb / Sillcock		Bathtub (and Shower)
		Floor Drain		Shower (Separate)
PIPING RELOCATION: of sanitary lines, drains, and piping without new fixtures.		Urinal		Sink
		Drinking Fountain		Wash Basin
<b>OR</b>  TRANSFER FEE [\$6.00]		Indirect Waste		Water Closet (Toilet)
		Water Treatment Softener, Filter, etc.		Clothes Washer
		Grease / Oil Separator		Dish Washer
		Dental Cuspidor		Garbage Disposal
		Bidet		Laundry Tub
		Other: _____		Water Heater
		<b>Fixtures (Subtotal) Column 2</b>		<b>Fixtures (Subtotal) Column 1</b>
				<b>Fixtures (Subtotal) Column 2</b>
			<u>3</u>	<b>Total Fixtures</b>
			\$	<b>Fixture Fee</b>
			\$	<b>Transfer Fee</b>
			\$	<b>Hook-Up &amp; Relocation Fee</b>
			\$	<b>Permit Fee (Total)</b>

SEE PERMIT FEE SCHEDULE FOR CALCULATING FEE