



DEMOLITION KEY NOTES:

- 1 REMOVE EXISTING THRESHOLD & OVERHEAD CLOSER HINGES.
- 2 REMOVE PARTITION COMPLETE.
- 3 REMOVE EXISTING CASEWORK COMPLETE.
- 4 REMOVE DOOR, FRAME AND HARDWARE COMPLETE.
- 5 REMOVE CEILING TILE AND GRID ASSEMBLY COMPLETE. COORDINATE EXTENTS OF REMOVAL WITH PARTITION LOCATIONS AND EXISTING FINISHES TO REMAIN.
- 6 REMOVE/RELOCATE EXISTING KITCHEN EQUIPMENT. REFERENCE AE101 AND FIELD VERIFY ALL SIZES.
- 7 REMOVE EXISTING PHONE BOOTHS.
- 8 REMOVE EXISTING DISPLAY BOARD AND RELOCATE (SEE AE101).
- 9 REMOVE ALL VINYL WALL COVERING IN ENTIRE WORK AREA AND PREP FOR PAINT FINISH.
- 10 REMOVE ALL CARPET TILE IN WORK AREA AND PREP FOR NEW FLOOR FINISHES.
- 11 REMOVE CHAIR RAIL.
- 12 REMOVE EXISTING SS COUNTER & WATER DISPENSER. RE:ELEC./MECH. DEMO.
- 13 REMOVE ALL CEILING TILE AND REMOVE GRID ASSEMBLY AS NECESSARY TO DO MECHANICAL DUCTWORK/PIPING.
- 14 REMOVE EXISTING QUARRY TILE.
- 15 ALTERNATE 1-REMOVE CEILING TILE AND GRID ASSEMBLY AS SHOWN.

GENERAL DEMOLITION NOTES:

- 1. COORDINATE EXTENT OF DEMOLITION WITH LOCATIONS OF PARTITIONS DESCRIBED ON PLANS AND WITH LOCATIONS OF FINISHES NOTED AS EXISTING TO REMAIN.
- 2. ANY WALL, PARTITION OR SURFACE DISTURBED BECAUSE OF NEW WORK OR DEMOLITION SHALL BE PATCHED AND FINISHED CONTINUOUSLY TO THE NEAREST CORNER UNLESS NOTED OTHERWISE. MATCH EXISTING ADJACENT CONSTRUCTION FINISHES, CONTINUITY AND FIRE RATINGS UNLESS NOTED OTHERWISE.
- 3. PROTECT ALL FINISHES, MATERIALS AND EQUIPMENT NOTED AS EXISTING TO REMAIN. CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ALL FINISHES, MATERIALS AND EQUIPMENT DAMAGED DURING CONSTRUCTION.
- 4. FOR EXTENTS OF CEILING GRID REMOVALS AND ADJUSTMENTS REFER TO SHEET AE???
- 5. DIMENSIONS INDICATED ± ARE EXISTING CONDITION DIMENSIONS TO BE VERIFIED IN FIELD.
- 6. REMOVE EXISTING RESILIENT BASE THROUGHOUT EXTENT OF WORK AREA.

CEILING DEMOLITION LEGEND

- SUSPENDED CEILING PANEL AND GRID ASSEMBLY TO BE REMOVED.
- SUSPENDED CEILING PANEL AND GRID ASSEMBLY TO REMAIN.
- 1x4 LIGHT FIXTURE TO BE REMOVED.

0	ISSUED FOR CONSTRUCTION	6-2-03
REV.	DESCRIPTION	DATE

ISSUED FOR CONSTRUCTION
6-2-03

CURRENT ISSUE STATUS:

--	--	--

SMRT ARCHITECTURE ENGINEERING PLANNING
144 Fore Street, P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070

UNUMPROVIDENT H01
THE BEACON
PORTLAND, ME.

PROJECT: **DEMOLITION FLOOR PLAN**

SHEET TITLE:	
SCALE: 1/8"=1'-0"	DATE: 6-2-03
PROJECT MANAGER: JLH	GRAPHIC SCALE: 0" 1"
JOB CAP/DRAWN: RJL	
A/E OF RECORD: JLH	SHEET No.
SMRT CAD FILE: AD101-02140	AD101
PROJECT No. 02140	