	ITEM	FURNISHED BY	INSTALLED BY	OTHER
AL CONTRACTOR AUDIOVISUAL CONTRACTOR	All Low Voltage Audiovisual Cabling	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	
	All Low Voltage Audiovisual Cable Terminations	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	
	Ceiling Speakers (with back boxes, transformers & grilles)	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	Related Construction, per Architectural details, to be furnished & installed by the General Contractor.
	Video Cameras	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	Related Construction, per Architectural details, to be furnished & installed by the General Contractor.
	AV Consoles and AV Equipment Cabinets	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	
	Wall Mounted Flat Screen Video Displays	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	Related Construction, per Architectural details, to be furnished & installed by the General Contractor.
	Ceiling Mounted Flat Screen Video Displays	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	Related Construction, per Architectural details, to be furnished & installed by the General Contractor.
	Electronic Dry Marker White Boards	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	Related Construction, per Architectural details, to be furnished & installed by the General Contractor.
	Table Microphones	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	
	Touch Screen Control Panels	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	
	Testing & Commissioning of the AV Systems	Audiovisual Contractor	Audiovisual Contractor	
	Bringing all AV equipment from the loading dock to the appropriate secured location.	Audiovisual Contractor	Union Electrical Contractor subcontracted by Audiovisual Contractor	
	Containment, conduit, junction boxes, AV floor boxes, wireways and other electrical (construction related) rough-in work pertaining to the installation of the AV systems. All devices as detailed on drawing AV-102, unless otherwise stated elsewhere in this chart.	Electrical Contractor	Electrical Contractor	All low voltage AV junction boxes shall be furnished with blank coverplates Cover plates shall be engraved and connectorized as required by the Audiovisual Contractor.
	All AC Power Receptacles and related Electrical Requirements as outlined within these AV design documents.	Electrical Contractor	Electrical Contractor	
	All Voice/Data provisions and related Telecommunications work as outlined within these AV design documents.	Electrical Contractor and/or IT Contractor	Electrical Contractor and/or IT Contractor	
	Lighting & Dimmer Systems	Electrical Contractor	Electrical Contractor	All lighting & dimmer systems will be specified by the Electrical Engineer and / or the Lighting Consultant. Refer to CMS drawings for recommended lighting zones and controls.
	Window Treatments (Drapes, Shades, Blinds). Where applicable, motorized systems shall be furnished with low voltage interface and wall switch.	General Contractor	General Contractor	Motorized drape/shade systems will be connected by the Electrical Contractor.
GENER				
NDOR	Lectern	Furniture Vendor	Furniture Vendor	Hatches, cutouts, grommets, access panels and all other modifications & accessories for the table shall be furnished and installed by the Furniture Vendor.
IITURE VE	Conference Tables	Furniture Vendor	Furniture Vendor	Hatches, cutouts, grommets, access panels and all other modifications & accessories for the table shall be furnished and installed by the Furniture Vendor.
7 FURN				
I-June-2017 VNER	All Computers with Keyboard & Mouse as required for AV Systems	Owner	Owner	
(RTW) 01-Ju OWNE	CABLE TV SERVICE and tuner boxes	Owner	Electrical Contractor and/or IT Contractor	



Gensler

214 North Tryon Street Suite 2320 Charlotte, NC 28202 United States

Tel 704.377.2725 Fax 704.377.2807

08/25/2017 REVIEW & COORDINATION

09/1/2017 REVIEW & COORDINATION

Seal / Signature

NOT FOR CONSTRUCTION

Unum Workplace Transformation- Phase 1 (HO2)

59.6481.003

AUDIOVISUAL SCOPE OF RESPONSIBILITIES

Scale 1/8" = 1'-0"

KEY PLAN

AV.101.00