



- GENERAL NOTES:**  
(APPLY THIS SHEET ONLY)
- COORDINATE ALL DEVICE LOCATIONS AND MOUNTING HEIGHTS WITH THE ARCHITECT & FURNITURE VENDOR PRIOR TO INSTALLATION.
  - HATCHED AREA NOT IN THIS SCOPE OF WORK.
  - 'E' DENOTES EXISTING DEVICE TO REMAIN. 'R' DENOTES EXISTING DEVICE TO BE RELOCATED.
  - VERIFY PROPER FUNCTIONALITY OF ALL EXISTING AND RELOCATED ELECTRICAL DEVICES, INCLUDING THEIR COVERPLATES. PROVIDE REPLACEMENTS AS REQUIRED IF ANY ARE NOT OPERATING AS INTENDED OR HAVE ABOVE NORMAL WEAR OR DEFECTS.
  - ALL ABANDONED AND UNUSED JUNCTION BOXES, BOXES WITH BLANK COVERPLATES, AND DATA OUTLET LOCATIONS NOT SHOWN ON THIS PLAN ARE TO BE DEMO'D. PATCH ANY EXISTING TO REMAIN WALLS TO A LIKE NEW CONDITION. ANY RECEPTACLE, WITHIN THE SCOPE OF WORK AREA, NOT SHOWN TO REMAIN SHALL BE REMOVED. ALL ASSOCIATED CONDUIT AND WIRING SHALL BE REMOVED BACK TO ITS SOURCE.
  - DEDICATED OUTLETS SHALL BE 20A RATED, U.N.O.
  - COORDINATE ALL SAW CUTTING LOCATIONS THROUGH THE SLAB WITH THE ARCHITECT AND LANDLORD PRIOR TO CUTTING. FOR ANY SLAB WITH POST-TENSION CABLING A SCAN SHALL BE PROVIDED TO LOCATED ANY OBSTRUCTIONS.
  - RECEPTACLES SHALL BE INSTALLED PER ANSI A117.1.
  - LABEL ALL OUTLETS, DEVICES, POWER POLES, JUNCTION BOXES, ETC... WITH THE CORRESPONDING CIRCUIT DESIGNATION. LABEL TO BE TYPED/WRITTEN; BLACK LETTERS ON WHITE BACKGROUND.
  - CIRCUIT HOMERUN DESIGNATIONS ARE NOTED FOR DESIGN INTENT ONLY BASED ON FIELD OBSERVATIONS OF EXISTING PANEL SCHEDULES, WHERE AVAILABLE. CONTRACTOR TO CONFIRM ALL SPARE CIRCUIT BREAKERS AND THOSE MADE AVAILABLE DUE TO DEMOLITION.
  - PROVIDE PULL STRINGS FOR ALL EMPTY CONDUIT. EACH NON-TERMINATED CONDUIT END SHALL BE PROVIDED WITH A BUSHING.
  - DIVISION 26 CONTRACTOR SHALL COORDINATE WITH DIVISION 23 TO MAKE SURE RETURN AIR OPENINGS ARE KEPT CLEAR OF ANY CONDUITS.

- LEGEND NOTES:**  
(APPLY THIS SHEET ONLY)
- RELOCATE EXISTING DEDICATED OUTLET FOR SOUND MASKING SYSTEM INTO ELECTRICAL ROOM. EXACT LOCATION IN THE ROOM TO BE COORDINATE WITH THE LANDLORD.

**unum**  
2211 Congress Street  
Portland, ME 04122

**Gensler**  
214 North Tryon Street  
Suite 2320  
Charlotte, NC 28202  
United States  
Tel: 704.377.2725  
Fax: 704.377.2807

**BW & A**  
Jeffrey Scott Lowery, P.E.  
420 Mineral Line  
Charlotte, NC 28217  
Tel: 704.357.9333  
MEP JOB# 170358

Date	Description
08.18.2017	ISSUE FOR PERMIT AND CONSTRUCTION

Seal / Signature

Project Name: 08/18/17

**Unum Workplace**  
Transformation- Phase 1 (H02)  
Project Number  
59.6481.000  
Description  
GROUND FLOOR PLAN (EAST) - ELECTRICAL

Scale  
1/8" = 1'-0"

**E1.100E**