ABBREVIATIONS

$	DOLLARS
&	AND
ACCES	ACCESSORY
ACOUS	ACOUSTIC(AL)
AFF	ABOVE FINISHED FLOOR
AL	ALUMINUM
ALT	ALTERNATE
ANNUNC	ANNUNCIATOR
ANOD	ANODIZED
APPL	APPLIANCE
ARCH	ARCHITECTURAL
AUTO	AUTOMATIC
AVG	AVERAGE
BD	BOARD
BLDG	BUILDING
BLKG	BLOCKING
BOLLD	BOLLARD
BRDLM	BOARDLOOM
BU	BUILT UP
CAB	CABINET
CEM	CEMENT(ITIOUS)
CER	CERAMIC
CJ	CONTROL JOINT
CLG	CEILING
CMU	CONCRETE MASONRY UNIT
COATG	COATING
COILG	COILING
CONC	CONCRETE
CONSTR	CONSTRUCTION
CONT	CONTINUOUS(ATION)
CONTR	CONTRACT(OR)
COV	COVER
CPT	CARPET
DBL	DOUBLE
DEPT	DEPARTMENT
DES	DESIGN(ED)
DET	DETAIL
DF	DRINKING FOUNTAIN
DIA	DIAMETER
DIFF	DIFFUSER
DIM	DIMENSION
DISP	DISPENSER
DIV	DIVISION
DN	DOWN
DR	DOOR
DSCON	DISCONNECT
DWR	DRAWER
ELAST	ELASTOMRIC
ELEC	ELECTRICAL
EMBED	EMBEDD(ED)(ING)
ENGR	ENGINEER(ED)
ENTR	ENTRANCE
EQ	EQUAL
EQUIP	EQUIPMENT
EXIST	EXISTING
EXP JT	EXPANSION JOINT
EXPS	EXPOSE(D)
EXT	EXTERIOR
FAB	FABRICATION
FD	FLOOR DRAIN
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER AND CABINET
FHC	FIRE HOSE CABINET
FIN	FINISH
FLDG	FOLDING
FLR	FLOOR(ING)
FPLC	FIREPLACE
FR	FIRE RAT(ING)(ED)
FRMG	FRAMING
FURN	FURNITURE
FWC	FABRIC WALL COVERING
FXD	FIXED
FXTR	FIXTURE
GA	GAUGE
GFRC	GLASS FIBER REINFORCED CONCRETE
GFRG	GLASS FIBER REINFORCED GYPSUM
GFRP	GLASS FIBER REINFORCED PLASTER
GL	GLASS
GR	GRAD(E)(ING)
GYP	GYPSUM
HD	HEAD
HDWD	HARDWOOD
HDWE	HARDWARE
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HVAC	HEATING, VENTILATING, AND AIR CONDITIONING
INFILTR	INFILTRATION
INFO	INFORMATION
INSTRUM	INSTRUMENT(ATION)
INSUL	INSULATION
INT	INTERIOR
INTLK	INTERLOCK(ING)
JAN	JANITOR
KIT	KITCHEN
LAV	LAVATORY
LB	POUND
LT	LIGHT
LVLG	LEVELING
LVR	LOUVER
MAX	MAXIMUM
MECH	MECHANICAL
MEMB	MEMBRANE
MET	METAL
MEZZ	MEZZANINE
MFD	MANUFACTURED
MFR	MANUFACTURER
MIN	MINIMUM
MISC	MISCELLANEOUS
MLWK	MILLWORK
MOIST	MOISTURE
MOT	MOTOR(IZED)
MTD	MOUNTED
NIC	NOT IN CONTRACT
NO	NUMBER
NTS	NOT TO SCALE
OPNG	OPENING(S)
OPR	OPERABLE
ORNA	ORNAMENTAL
OVFL	OVERFLOW
OVHD	OVERHEAD
PBD	PARTICLE BOARD
PEDTR	PEDESTRIAN
PLAM	PLASTIC LAMINATE
PLAS	PLASTER
PLSTC	PLASTIC
PLYWD	PLYWOOD
PNL	PANEL
POLYST	POLYSTYRENE
PORT	PORTABLE
PREFAB	PREFABRICATED
PREFIN	PREFINISHED
PRTECN	PROTECTION
PTN	PARTITION
RDR	READER
RECES	RECESSED
RECPT	RECEPTACLE
REF	REFER(ENCE)
REFL	REFLECTED
REFR	REFRIGERATOR
REINF	REINFORCE(D)(ING)(MENT)
REQD	REQUIRED
RESIL	RESILIENT
RESIS	RESIST(ANT)(IVE)
RFG	ROOFING
RM	ROOM
RO	ROUGH OPENING
SCR	SCRIBE
SECUR	SECURITY
SF	SQUARE FEET
SGL	SINGLE
SHORG	SHORING
SIM	SIMILAR
SST	STAINLESS STEEL
STD	STANDARD
STL	STEEL
STRFR	STOREFRONT
STRUCT	STRUCTURAL
SURF	SURFACE
SUSP	SUSPENDED
SYS	SYSTEM(S)
T&G	TONGUE AND GROOVE
THK	THICK
TLT	TOILET
TRAF	TRAFFIC
TRANS	TRANSPARENT
TRTD	TREATED
TYP	TYPICAL
UNDRLAY	UNDERLAYMENT
UNO	UNLESS NOTED OTHERWISE
UTIL	UTILITY
VEH	VEHICLE
VERT	VERTICAL
VIF	VERIFY IN FIELD
W/	WITH
W/O	WITHOUT
WC	WATER CLOSET
WD	WOOD
WDW	WINDOW
WT	WEIGHT
WTRPRF	WATERPROOFING
£	BRITISH POUND (CURRENCY)

GRAPHICS SYMBOLS (CONT.)

ELEVATION INDICATIONS

GLASS SYMBOL
MASONRY COURSING
WOOD VENEER
STONE

SECTION INDICATIONS

ACOUSTICAL CEILING TILE
ALUMINUM
BRICK
CARPET
CONCRETE
CONCRETE MASONRY UNIT
CUTSTONE
EARTH OR GROUND
FABRIC WRAPPED PANEL
GLASS
GRAVEL
GYPSUM BOARD
INSULATION (LOOSE OR BATT)
INSULATION (RIGID)
METAL
PLASTER
PLASTER/LATH
PLYWOOD
PRE-CAST PANELS
SAND OR GROUT
STONE
WOOD (FINISHED)
WOOD (CONTINUOUS MEMBER)
WOOD (INTERRUPTED MEMBER)

GRAPHICS SYMBOLS (CONT.)

REFLECTED CEILING

ACOUSTICAL CEILING AND GRID
CEILING HEIGHT CHANGE SYMBOL
FINISH CEILING HEIGHT SYMBOL
GRID STARTPOINT SYMBOL
CEILING FINISH TAG
CEILING MOUNTED SPEAKER
CEILING MOUNTED SPRINKLER HEAD
CEILING MOUNTED SMOKE DETECTOR
CEILING MOUNTED EXIT SIGN
WALL MOUNTED EXIT SIGN
E DENOTES EXISTING TO REMAIN
R DENOTES EXISTING TO BE RELOCATED
CEILING MOUNTED ANTENNA

LIGHT FIXTURES

FLUORESCENT LIGHT FIXTURE
FLUORESCENT LIGHT FIXTURE / EMERGENCY CIRCUIT
EXISTING LIGHT FIXTURE TO BE REMOVED
UNDER CABINET FLUORESCENT FIXTURE
FLUORESCENT STRIP FIXTURE
FLUORESCENT PENDANT FIXTURE
RECESSED DOWNLIGHT
RECESSED ADJUSTABLE DOWNLIGHT
RECESSED WALL WASHER
TRACK LIGHTING
SURFACE MOUNTED LIGHT FIXTURE
WALL SCONCE
LIGHT SWITCH
D DIMMER SWITCH

MECHANICAL FIXTURES

RETURN AIR
SUPPLY AIR
CIRCULAR DIFFUSER
LINEAR DIFFUSER
EF EXHAUST FAN
FIRE SPRINKLER
ACCESS DOOR
CO2 CO2 DETECTOR

GRAPHICS SYMBOLS (CONT.)

POWER AND COMMUNICATION, CONT

SURFACE FLOOR MOUNTED, POKE THRU DEVICES

SURFACE FLOOR MOUNTED, POKE THRU, SINGLE RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, DUPLEX RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, QUADRAPLEX RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, COMBINATION DUPLEX & VOICE/DATA RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, COMBINATION QUADRAPLEX & VOICE/DATA RECEPTACLES
SURFACE FLOOR MOUNTED, POKE THRU, COMBINATION DUPLEX, AUDIO VISUAL AND VOICE/DATA RECEPTACLES
SURFACE FLOOR MOUNTED, POKE THRU, COMBINATION QUADRAPLEX, AV & VOICE/DATA RECEPTACLES
SURFACE FLOOR MOUNTED, POKE THRU, VOICE/DATA RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, DATA RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, VOICE RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, AV RECEPTACLE
SURFACE FLOOR MOUNTED, POKE THRU, SYSTEMS WORKSTATION PANEL POWER INFEED
SURFACE FLOOR MOUNTED, POKE THRU, SYSTEMS WORKSTATION PANEL VOICE INFEED

FURNITURE SYSTEMS MOUNTED DEVICES

FURNITURE SYSTEMS MOUNTED, SINGLE RECEPTACLE
FURNITURE SYSTEMS MOUNTED, DUPLEX RECEPTACLE
FURNITURE SYSTEMS MOUNTED, QUADRAPLEX RECEPTACLE
FURNITURE SYSTEMS MOUNTED, VOICE/DATA RECEPTACLE
FURNITURE SYSTEMS MOUNTED, DATA RECEPTACLE
FURNITURE SYSTEMS MOUNTED, VOICE RECEPTACLE
FURNITURE SYSTEM ELECTRIC PIGTAIL
PP FURNITURE MOUNTED, POWER POLE

SECURITY DEVICES

CAMERA
CR CARD READER
B ELECTRIC DOOR BELL PUSH
B ELECTRIC DOOR BELL
IC INTERCOM
DR REMOTE DOOR RELEASE BUTTON
MS MOTION SENSOR
IA INTRUSION ALARM
EH ELECTRIC DOOR HINGE
H ELECTRICAL DOOR HOLD OPEN
DR ELECTRICAL DOOR RELEASE
DC ELECTRICAL DOOR MONITOR CONTACT
DDC DOUBLE DOOR MONITOR CONTACT
EL ELECTRIC LOCKSET
KS ELECTRIC KEY SWITCH
ES ELECTRIC STRIKE
ML MAGNETIC LOCKSET
PB PANIC BUTTON
VC VOICE CALL
RS ROOM SCHEDULER

GRAPHICS SYMBOLS (CONT.)

POWER AND COMMUNICATION

WALL MOUNTED DEVICES

XX EQUIPMENT TAG (REFER TO EQUIPMENT SCHEDULE)
WALL MOUNTED, SINGLE RECEPTACLE
WALL MOUNTED, DUPLEX RECEPTACLE
WALL MOUNTED, QUADRAPLEX RECEPTACLE
WALL MOUNTED, VOICE/DATA RECEPTACLE
WALL MOUNTED, DATA RECEPTACLE
WALL MOUNTED, VOICE RECEPTACLE
T WALL MOUNTED, THERMOSTAT
CTV WALL MOUNTED, CABLE TV RECEPTACLE
AV WALL MOUNTED, AV RECEPTACLE
AV WALL MOUNTED, AV TROUGH
WALL MOUNTED, ELECTRICAL JUNCTION BOX
WALL MOUNTED, VOICE/DATA JUNCTION BOX
P WALL MOUNTED, SYSTEMS WORKSTATION PANEL POWER INFEED
V WALL MOUNTED, SYSTEMS WORKSTATION PANEL VOICE/DATA INFEED
WALL MOUNTED, CONDUIT STUB-OUT POWER
WALL MOUNTED, CONDUIT STUB-OUT VOICE AND DATA
WALL MOUNTED, CONDUIT STUB-OUT A/V
WALL MOUNTED, PLUG MOLD

FLUSH FLOOR MOUNTED DEVICES

FLUSH FLOOR MOUNTED, SINGLE RECEPTACLE
FLUSH FLOOR MOUNTED, DUPLEX RECEPTACLE
FLUSH FLOOR MOUNTED, QUADRAPLEX RECEPTACLE
FLUSH FLOOR MOUNTED, COMBINATION DUPLEX & VOICE/DATA RECEPTACLE
FLUSH FLOOR MOUNTED, COMBINATION QUADRAPLEX & VOICE/DATA RECEPTACLES
FLUSH FLOOR MOUNTED, COMBINATION DUPLEX, AUDIO VISUAL AND VOICE/DATA RECEPTACLES
FLUSH FLOOR MOUNTED, COMBINATION QUADRAPLEX, AV & VOICE/DATA RECEPTACLES
FLUSH FLOOR MOUNTED, VOICE/DATA RECEPTACLE
FLUSH FLOOR MOUNTED, DATA RECEPTACLE
FLUSH FLOOR MOUNTED, VOICE RECEPTACLE
P FLUSH FLOOR MOUNTED, SYSTEMS WORKSTATION PANEL POWER INFEED
V FLUSH FLOOR MOUNTED, SYSTEMS WORKSTATION PANEL VOICE INFEED
AV FLUSH FLOOR MOUNTED, AV RECEPTACLE
PVD FLUSH FLOOR MOUNTED, RAISED FLOOR BOX, COMBINATION POWER, VOICE/DATA
PVA FLUSH FLOOR MOUNTED, RAISED FLOOR BOX, COMBINATION POWER, VOICE/DATA, A/V
AV FLUSH FLOOR MOUNTED, RAISED FLOOR BOX, AV

FLUSH FLOOR MOUNTED, POKE THRU, DEVICES

FLUSH FLOOR MOUNTED, POKE THRU, SINGLE RECEPTACLE
FLUSH FLOOR MOUNTED, POKE THRU, DUPLEX RECEPTACLE
FLUSH FLOOR MOUNTED, POKE THRU, QUADRAPLEX RECEPTACLE
FLUSH FLOOR MOUNTED, POKE THRU, COMBO DUPLEX & VOICE/DATA RECEPTACLE
FLUSH FLOOR MOUNTED, POKE THRU, COMBINATION QUADRAPLEX & VOICE/DATA RECEPTACLES
FLUSH FLOOR MOUNTED, POKE THRU, COMBINATION DUPLEX, AUDIO VISUAL AND VOICE/DATA RECEPTACLES
FLUSH FLOOR MOUNTED, POKE THRU, COMBINATION QUADRAPLEX, AV & VOICE/DATA RECEPTACLES
FLUSH FLOOR MOUNTED, POKE THRU, VOICE/DATA RECEPTACLE
FLUSH FLOOR MOUNTED, POKE THRU, DATA RECEPTACLE
FLUSH FLOOR MOUNTED, POKE THRU, VOICE RECEPTACLE
FLUSH FLOOR MOUNTED, POKE THRU, AV RECEPTACLE
P FLUSH FLOOR MOUNTED, POKE THRU, SYSTEMS WORKSTATION PANEL POWER INFEED
V FLUSH FLOOR MOUNTED, POKE THRU, SYSTEMS WORKSTATION PANEL VOICE INFEED

SURFACE FLOOR MOUNTED DEVICES

SURFACE FLOOR MOUNTED, SINGLE RECEPTACLE
SURFACE FLOOR MOUNTED, DUPLEX RECEPTACLE
SURFACE FLOOR MOUNTED, QUADRAPLEX RECEPTACLE
SURFACE FLOOR MOUNTED, COMBINATION DUPLEX & VOICE/DATA RECEPTACLE
SURFACE FLOOR MOUNTED, COMBINATION QUADRAPLEX & VOICE/DATA RECEPTACLES
SURFACE FLOOR MOUNTED, COMBINATION DUPLEX, AUDIO VISUAL AND VOICE/DATA RECEPTACLES
SURFACE FLOOR MOUNTED, COMBINATION QUADRAPLEX, AV & VOICE/DATA RECEPTACLES
SURFACE FLOOR MOUNTED, VOICE/DATA RECEPTACLE
SURFACE FLOOR MOUNTED, DATA RECEPTACLE
SURFACE FLOOR MOUNTED, VOICE RECEPTACLE
P SURFACE FLOOR MOUNTED, SYSTEMS WORKSTATION PANEL POWER INFEED
V SURFACE FLOOR MOUNTED, SYSTEMS WORKSTATION PANEL VOICE INFEED
AV SURFACE FLOOR MOUNTED, AV RECEPTACLE
SURFACE FLOOR MOUNTED, CONDUIT STUB UP, POWER
SURFACE FLOOR MOUNTED, CONDUIT STUB UP, VOICE/DATA
SURFACE FLOOR MOUNTED, CONDUIT STUB UP, AV

GRAPHICS SYMBOLS

CONSTRUCTION

XX COLUMN GRID REFERENCE NUMBER
COLUMN GRID LINES AND REFERENCE NUMBER
EXISTING CONSTRUCTION TO REMAIN
EXISTING CONSTRUCTION TO BE DEMOLISHED
NEW PARTITION
1 HR. RATED PARTITION
2 HR. RATED PARTITION
3 HR. RATED PARTITION
4 HR. RATED PARTITION
SMOKE PARTITION
EGRESS PATH PRIMARY
EGRESS PATH SECONDARY
MILLWORK
MILLWORK ABOVE
XXXX DETAIL NUMBER
AXX.XX SHEET NUMBER
FL 12. NW Ref DESCRIPTION OF SIMILAR OR OPPOSITE
FLOOR NUMBER AND AREA OR PHASE
AREA TO BE DETAILED
A LOCATION ON ROW WHERE ELEVATION IS SHOWN
DIRECTION OF ELEVATION
01 ROW ON SHEET WHERE ELEVATION IS SHOWN
A11.XX SHEET NUMBER WHERE ELEVATION IS SHOWN
XX REVISION REFERENCE NUMBER
REVISION CLOUD DEPICTING ARE REVISED
Name 101 ROOM NAME
ROOM NUMBER
1 SHEETNOTE REFERENCE
XXXX WALL TYPE REFERENCE
XXXXXX DOOR REFERENCE NUMBER (REFER TO DOOR SCHEDULE)
XX DOOR TYPE
XX HARDWARE TYPE
XXXX DOOR NUMBER
XX.XX DOOR TYPE / HARDWARE TYPE
XXX WINDOW REFERENCE NUMBER (REFER TO WINDOW SCHEDULE)
XXXX MILLWORK REFERENCE NUMBER (REFER TO MILLWORK SCHEDULE)
Name Elevation ELEVATION DATUM REFERENCE
MATCH LINE SYMBOL
ALIGN ALIGN WITH ESTABLISHED SURFACES

WALL MOUNTED LIFE SAFETY EQUIPMENT AND DEVICES

FW FIRE WARDEN STATION SYMBOL
ST WALL MOUNTED FIRE ALARM STROBE SYMBOL
FA FIRE ALARM PULL SYMBOL
FEC WALL MOUNTED, FIRE EXTINGUISHER CABINET
FE WALL MOUNTED FIRE EXTINGUISHER
FHC WALL MOUNTED FIRE HOSE CABINET
FV WALL MOUNTED FIRE VALVE
FVC WALL MOUNTED FIRE VALVE CABINET

FINISH

XXX WALL FINISH
XXX BASE FINISH
XXX WALL FINISH
XXX WALL FINISH
XXX WAINSCOT FINISH
XXX BASE FINISH
EXTENT OF WALL / WAINSCOT / BASE FINISH
? SPECIAL FINISH / FINSIH IN ELEVATION
XX FLOOR FINISH
CEILING FINISH
CHANGE IN FLOOR FINISH

unum
2211 Congress Street
Portland, ME 04122

Gensler
214 North Tryon Street
Suite 2320
Charlotte, NC 28202
United States
Tel 704.377.2725
Fax 704.377.2807

Date	Description
08/18/17	DEMOLITION & EARLY WORK

Seal / Signature

LICENSED ARCHITECT DOUGLAS C. GENSLER 2950 STATE OF MAINE

Project Name
Unum Workplace Transformation- Phase 1 (HO2)

Project Number
59.6481.003

Description
GRAPHIC SYMBOLS AND ABBREVIATIONS

Scale
1/8" = 1'-0"

G00.003

© 2015 Gensler

8/18/2017 6:01:09 PM \\gensler.at\projects\Revit\UserModels\246\59\6481.003 - UNUM - PORTLAND - HO2_2016_MichaelThomas\Gensler.rvt