SINK OR VANITY
SCALE: 1/2" = 1-'0"

DRINKING FOUNTAIN
SCALE: 1/2" = 1-'0"

REACH RANGES/CLR FLR
SCALE: 1/2" = 1-'0"

CLEARANCES
SCALE: 1/4" = 1-'0"

HANDRAIL EXTENSIONS
SCALE: 1/2" = 1-'0"

PROTRUDING OBJECTS
SCALE: 1/4" = 1-'0"

LEVEL CHANGES
SCALE: 1'-0" = 1-'0"

17 LOCATIONS at CREDENZAS or COUNTERS OUTLETS

18 LOCATIONS at CREDENZAS or COUNTERS SWITCHES and THERMOSTATS

19 LOCATION FOR TYPICAL SIGNS

20 LOCATIONS at WORK SURFACES OUTLETS

21 LOCATIONS at MILLWORK COUNTERS OUTLETS

22 LOCATIONS at MILLWORK COUNTERS OUTLETS

NOTES: (APPLIES TO POWER, PHONE, COMMUNICATIONS, ETC.)
1. PLACE OUTLET BOXES IN SEPARATE STUD SPACES.
2. BACK-TO-BACK OUTLETS NOT PERMITTED.
3. PLUG ALL UNUSED KNOCK-OUTS IN OUTLET BOXES WITH KNOCK-OUT CAPS.
4. PROVIDE BACKING EQUIVALENT TO "LOWRY'S OUTLET BOX PADS (HARRY A. LOWRY & ASSOC.)
5. DEPTH OF OUTLET BOX MUST BE COMPATIBLE W/ STUD SIZE IN ORDER TO ACCOMODATE BOX PAD.
6. ACOUSTICAL BOX PAD REQUIREMENT APPLIES TO ALL PARTITIONS WITH ACOUSTIC INSULATION.

BACK TO BACK OUTLET BOX DETAIL
SCALE: 1 1/2" = 1-'0"

9 LOCATIONS at COLUMNS, BETWEEN DOORS, ETC. OUTLET GROUPS, STROBES and THERMOSTATS

10 LOCATIONS at COLUMNS, BETWEEN DOORS, ETC. SWITCHES, STROBES and THERMOSTATS

11 LOCATIONS at COLUMNS, BETWEEN DOORS, ETC. OUTLETS, STROBES and FIRE ALARM PULLS

12 LOCATIONS at CORNERS OUTLETS

13 LOCATIONS at CORNERS SWITCHES, OUTLETS, STROBES and THERMOSTATS

14 LOCATIONS at CORNERS OUTLETS, STROBES and THERMOSTATS

15 LOCATIONS at CORNERS with REVEALS STROBES and THERMOSTATS

16 LOCATION FOR EXIT SIGNS (WALL MOUNTED)

1 LOCATIONS at DOOR JAMBS SWITCH and THERMOSTAT

2 LOCATIONS at DOOR JAMBS SWITCH and TELEPHONE

3 LOCATIONS at DOOR JAMBS CARD READER, EGRESS BUTTON or FIRE ALARM PULL

4 LOCATIONS at DOOR JAMBS THERMOSTAT, STROBE or OUTLET

5 LOCATIONS at OPEN DOORS SWITCHES, STROBES and THERMOSTATS

6 LOCATIONS at COLUMNS, BETWEEN DOORS, ETC. OUTLETS, STROBES and THERMOSTATS

7 LOCATIONS at FREIGHT ELEVATORS STROBES

8 LOCATIONS at FIRE EXTINGUISHER CABINET STROBES and FIRE ALARM PULLS

unum
2211 Congress Street
Portland, ME 04122

Gensler
214 North Tryon Street
Suite 2320
Charlotte, NC 28202
United States
Tel 704.377.2725
Fax 704.377.2807

Approved for Code Compliance
Approved with Conditions
Disapproved with Conditions
Date: _____

Date	Description
08/18/17	DEMOLITION & EARLY WORK

Seal / Signature

LICENSED ARCHITECT
DOUGLAS C. GENSLER
2950
STATE OF MAINE

Project Name
Unum Workplace Transformation- Phase 1 (HO2)

Project Number
59.6481.003

Description
ADA INFORMATION & TYPICAL MOUNTING HEIGHTS

Scale
As indicated

G00.002

© 2015 Gensler

8/18/2017 6:01:08 PM \\gensler.adr\projects\Revit\UserModels\224525\9481.003 - UNUM - PORTLAND - HO2_2016_MichaelThomasGensler.rvt