

## DOOR SCHEDULE

NUMBER	LOCATION	TYPE	DOOR MATERIAL	FINISH	WIDTH	HEIGHT	FRAME MATERIAL	FRAME FINISH	FIRE RATING	HARDWARE SET	COMMENTS
GROUND FLOOR											
2.0.C.500	FITNESS CENTER	CC									
2.0.C.501	FITNESS CENTER	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	1	
2.0.C.501	GROUP CLASSROOM	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	1	
2.0.C.505A	DAY LOCKERS	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	2	
2.0.C.505B	DAY LOCKERS	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	2	
2.0.C.506	RESTROOM	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	3	
2.0.C.506	MENS LOCKER ROOM	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	1	
2.0.C.509	RESTROOM	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	3	
2.0.C.511	MASSAGE ROOM	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	3	
2.0.C.512	WOMENS LOCKER	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	1	
2.0.C.516	HRC OFFICE	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	4	
2.0.C.517	HRC EXAM	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	4	
2.0.C.520	HRC MIXED USE	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	4	
2.0.C.921	EXST	A	WD	PT	3'-0"	7'-0"	ALUM	PT	--	13	
2.0.E.402	STORAGE CHAIRS	B	WD	PT	6'-0"	9'-0"	ALUM	PT	--	2	
BATHROOM PARTITION											
N.	FITNESS CENTER	N			0'-0"	9'-4"			--		

## GLASS OFFICE FRONT DOOR SCHEDULE

NUMBER	LOCATION	TYPE	DOOR MATERIAL	FINISH	WIDTH	HEIGHT	FRAME MATERIAL	FRAME FINISH	FIRE RATING	HARDWARE SET	COMMENT
GROUND FLOOR											
02.0.C.500	FITNESS CENTER	PP	TEMPERED GL	-	6'-7 5/8"	10'-0"	ALUM	CLR ANODIZED	--	6	VIF OPENING DIMENSIONS TO CONFIRM WIDTH PER PLAN.
02.0.C.500A	OFFICE	J	TEMPERED GL	-	3'-0"	10'-0"	ALUM	CLR ANODIZED	--	5	
02.0.C.500B	SPIN ROOM	J	TEMPERED GL	-	3'-4"	10'-0"	ALUM	CLR ANODIZED	--	5	
02.0.C.500C	FITNESS CENTER	J	TEMPERED GL	-	3'-4"	10'-0"	ALUM	CLR ANODIZED	--	5	
02.0.C.516	CIRCULATION	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.307A	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.307B	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.307D	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.307E	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.307F	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.307G	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308A	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308B	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308C	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308D	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308E	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308F	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308G	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.308H	TRAINING	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.A	CONFERENCE	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	
02.0.E.I	CONFERENCE	J	TEMPERED GL	-	3'-4"	9'-4"	ALUM	CLR ANODIZED	--	6	



2211 Congress Street  
Portland, ME 04122


**Gensler**

214 North Tryon Street  
Suite 2320  
Charlotte, NC 28202  
United States

Tel 704.377.2725  
Fax 704.377.2807

Date	Description
12/15/17	ISSUE FOR PERMIT & CONSTRUCTION

Seal / Signature



Project Name

Unum Workplace Transformation  
- Phase 2 & 3 (HO2 & HO3)

Project Number

59.6481.003

Description

DOOR SCHEDULE - HO2

Scale

**A00.012.3**

© 2015 Gensler